

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20563-00-00
Spot: SENENW Sec/Twnshp/Rge: 9-20S-12W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: TONKIN Well #: 1
County: BARTON Total Vertical Depth: 3428 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: PO BOX 70 234 W. 11TH, STE A
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3427	0	w/100 sxs cmt
SURF	8.625	208	0	w/225 sxs cmt

\$ 111.41

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2007 2:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DEAN IVES Company: DAMAR RESOURCES, INC. Phone: (785) 625-0020

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/14/2007 5:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Holes in casing at 1097' - 1425'.
Ran tubing to 2800' - pumped 100 sxs 60/40 pozmix - 10% gel cement.
Pulled to 1450' - pumped 140 sxs cement with 1000# hulls.
Pulled to 725' - circulated with 120 sxs inside 5 1/2"
POOH. Tied onto casing - pumped 40 sxs cement.
Cement circulated up backside.

Perfs:

INVOICED
DATE 3-27-07
INV. NO. 2007061503

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Case Morris
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 19 2007 Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

MAR 15 2007

PCT

NATIONAL OIL COMPANY
 WICHITA, KANSAS
 CONTR H-30, INC.

#1 TONKIN


9-20-12W
 SE NE NW

CTY BARTON

GEOL RAY GOODIN

FIELD TONKIN

E 1821 KB CM 1/9/71 CARD ISSUED 4/1/71 IP P 125 BOPD + 100 BWPD
 ARB 3382-3407



API 15-009-20,563

LOG	TOPS	DEPTH	DATUM	DESCRIPTION
			8 5/8" 208/2255x; 5 1/2" 3427/1005x	
			DST(1)	3141-75(LANS)/1', 30' THIN M, BHP 1155-1090#/30", FP 45-80#
ANHY	623	+1198		
Q.H.	2908	-1087	DST(2)	3170-3219/(LANS)/1', 1630' WTR, BHP 945-935#/30", FP 420-975#
HEEB	3003	-1182		
TOR	3028	-1207	DST(3)	3383-92(ARB)/1', 20' OCM, BHP 645-570#/30", FP 30-45#
DOUG	3038	-1217		
BN L	3122	-1301	DST(4)	3392-3411(ARB)/90", 90' OCM, BHP 705-695#/30", FP 30-85#
LANS	3137	-1316		
BKC	3371	-1550	DST(5)	3411-3428(ARB)/1', 10' FREE OIL + 240' OCW, BHP 935-905#/30", FP 45-140#
ARB	3379	-1558		
LTD	3412	-1591		
RTD	3428	-1607		

MICT, PF 3407-13, 3398-3408, 3382-90
 3500 GALS ACID SWB LD & SWB 24BFPH 40%
 OIL, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS