

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02268-00-00
Spot: SESENW Sec/Twnshp/Rge: 17-9S-16W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: FINNESY Well #: 1
County: ROOKS Total Vertical Depth: 3385 feet

Operator License No.: 8132
Op Name: H & H OIL COMPANY, A GENERAL PA
Address: 904 S SECTION LINE
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3380	0	w/unknown sxs cmt
SURF	8.625	210	0	w/unknown sxs cmt

\$ 110.01

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2007 9:00 AM
Plug Co. License No.: 32988 Plug Co. Name: HAMMERSCHMIDT, LEON DBA LEON'S DRILLING SERVICE
Proposal Rcvd. from: BILL HAMMERSCHMIDT Company: H&H OIL COMPANY Phone: (785) 635-1037

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2007 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 800' and 1250'.
TIH with tubing to 2000' - mixed and pumped 150 sxs cement with 200# hulls.
Pulled up to 900' and circulated cement with 95 sxs and 300# hulls.
POOH. Topped with 5 sxs cement. S.I.P. 700#.
Hooked up to 8 5/8" and pumped 50 sxs cement.
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3288	3323		

INVOICED

DATE 3-27-07

INV. NO. 2007061504

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

RECEIVED

MAR 23 2007

KCC WICHITA

MAR 20 2007

BRYANT OIL CO

#1

FINNESY

17-9-16W
SE SE NW

Contr. STEARNS DRLG

ROOKS

County

E 2018RB Comm.

Comp. 9-6-57

IP

36 BOPD

Tops	Depth	Datum
HEEB	3093	-1075
KC	3140	-1122
TD	3385	-1367

Casing

8" 210

5" 3380

CORRECTED CARD

9-20-57

PERF 3288-3323

ACID 10,000

DORR POOL

(CORRECTED LANSING
TOP & DATUM)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS