

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-00644-00-01

Spot: NENENE

Sec/Twnshp/Rge: 27-5S-21W

4950 feet from S Section Line,

330 feet from E Section Line

Lease Name: WILTROUT

Well #: 6

County: NORTON

Total Vertical Depth: 1840 feet

Operator License No.: 5252

Op Name: NIXON, R P OPERATIONS, INC

Address: 207 W 12TH  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	5.5	3642	0	175 SX
------	-----	------	---	--------

SURF	8.625	223	0	160 SX
------	-------	-----	---	--------

\$ 59.80

Well Type: SWD

UIC Docket No: D06484.0

Date/Time to Plug: 03/20/2007 10:30 AM

Plug Co. License No.: 5252

Plug Co. Name: NIXON, R P OPERATIONS, INC

Proposal Rcvd. from: DUANE ACHTERBERG

Company: NIXON, R P OPERATIONS, INC

Phone: (785) 656-0038

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 10% gel and hulls.  
PBSD 1840' for Cedar Hill SWD.

Plugging Proposal Received By: HERB DEINES

WitnessType: NONE

Date/Time Plugging Completed: 03/20/2007 11:00 AM

KCC Agent: HERB DEINES

Actual Plugging Report:

8 5/8" to 223' w/160 sxs. 5 1/2" to 3642' w/175 sxs.  
Alternate II cementing from 1825' to surface with 450 sxs.  
Tied onto annulus with instant 500# S.I.P.  
Tied onto production casing and pumped 200 sxs 60/40 pozmix - 10% gel with 600# hulls.  
Let set for one hour. Cement dropped 200' - 300'.  
Will top off with cement when well head cut off.

Perfs:

Top	Bot	Thru	Comments
3642	3661		REAGAN SAND
3572	3575		L/KC
3470	3472		L/KC
3438	3440		L/KC
1368	1538		CEDAR HILLS

INVOICED

DATE 3.27.07


INV. NO. 2007061514

Remarks: ALLIED CEMENTING COMPANY-TICKET #33111.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

RECEIVED

MAR 23 2007

KCC WICHITA

MAR 21 2007

JOCELYN-VARN OIL CO

#6 WILTROUT

27-5-21W

NE NE NE

Contr. TRUSCO DRUG CO

NORTON County

E 2223

Comm. 4-16-58

Comp. 5-16-58

IP

D &amp; A

Tops	Depth	Datum	Casing
HEEB	3363	-11140	8" 223
TOR	3390	-1167	5" 3642
LANS	3406	-1183	DST 3320-77/1 HR, 2376' FLD (480' M, 890' W) BHP 1200
			DST 3468-88/1 HR, 240' H OCM, 30' MDY SW, BHP 1232
			CO 3644: DD 3648: TST 5 GO & 5 GWPH:
			ACID 1500: DD 3661: TST 1 BWPH, SCM O,
			PERF 3572-3575: 12/3470-72: PERF 3438-40
ARB	3641	-1418	PLUG 3455: TST SSO & M: ACID 1000: TST
REAG	3660	-1437	31 B SWPH
TD	3661	-1438	

RAY WEST POOL


INDEPENDENT OIL &amp; GAS SERVICE