

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10631-00-00 ³¹²⁶¹⁰⁷
Spot: ^{NW} ~~NENENW~~ ^{per RBDMS} ~~PKT~~ Sec/Twnshp/Rge: 29-26S-12W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: PETROWSKY Well #: 2
County: PRATT Total Vertical Depth: 4326 feet

Operator License No.: 9232
Op Name: TIMBERLINE OIL & GAS CORPORATIO
Address: 4000 PENROSE PLACE
RAPID CITY, SD 57702

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3950		
CIBP		4300		
PROD	5.5	4325	50	WITH 200 SX CMT
SURF	8.625	410		WITH 275 SX CMT

\$ 140.60

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2007 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: AL BALNARO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: CIBP & 4 SX CMT. 1ST PLUG STUB PLUG (2100) WITH 50 SX CMT. PLUG AT 780' WITH 50 SX CMT. PLUG AT 430' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/20/2007 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

JUNK IN HOLE: 2 3/8" CMT LINED TUBING FROM 2135' TO STUCK PACKER AT 3800'. ATTEMPT TO PULL CASING, ABANDONED DUE TO CASING PARTING (TWICE). PUSHED WIPER PLUG TO 2100' (ON TOP OF TUBING FISH) SANDED BACK TO 2040' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. PERFORATED 5 1/2" CASING AT 2000', 780', & 430'. RUN IN WITH 2 3/8" TUBING. 1ST PLUG AT 2000' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 780' WITH 50 SX CMT. PULLED TUBING OUT OF HOLE. SDON & LET CMT SET. 02/20/07: RUN IN & TAG TOP OF CMT AT 580'. 3RD PLUG RUN TUBING IN TO 430'. CIRCULATED FROM 430' TO SURFACE WITH 100 SX CMT. PULLED TUBING OUT OF HOLE. ATTEMPT TO TOP OUT WELL. PUMPED 100 SX CMT. HOLE WOULD NOT LOAD. SHUT DOWN TO LET CMT STATIC OUT & SET. (HOLE TAKING CMT). RUN IN HOLE & TAG TOP CMT AT 100'. CIRCULATE HOLE THROUGH TUBING FROM 100' TO SURFACE WITH 40 SX CMT. HOLE STAYING FULL.

Perfs:

Top	Bot	Thru	Comments
4232	4239		
3916	3924		
3836	3844		SQUEEZED


INVOICED

DATE 3-27-07
INV. NO. 2007061517

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.

Plugged through: TBG

District: 01



Signed _____

Stephen J. Puffer
(TECHNICIAN)
KANSAS CORPORATION COMMISSION

RECEIVED
MAR 19 2007
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

PKT