

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22968-00-00

Spot: ~~SE~~^{SW}SWSE

Sec/Twnshp/Rge: 35-32S-12W

311 ~~330~~ feet from S Section Line, 1650 feet from E Section Line

Lease Name: BARTHOLOW B

1998 Well #: 1

County: BARBER

Total Vertical Depth: 4956 feet

KCC
PCT
3/26/07
GPS
FTG

Operator License No.: 33168

Op Name: WOOLSEY OPERATING COMPANY, LL

Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4610		WITH 2 SX CMT
PROD	4.5	4784	3300	WITH 315 SX CMT
SURF	10.75	239		WITH 200 SX CMT

\$ 101.07

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/06/2007 1:15 PM

Plug Co. License No.: 5105

Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: JOHN SWINFORD

Company: CLARKE CORPORATION

Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4610' & 2 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 270' WITH 80 SX CMT. PLUG AT 60' WITH 25 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/06/2007 2:00 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4610' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 270' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4660	4666		

INVOICED


DATE 3-27-07

INV. NO. 2007061522

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Stephen J Pfeifer
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

MAR 19 2007

CONSERVATION DIVISION
WICHITA, KS

PCT