

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Krier Oil Operations

Address: P.O. Box 763, Great Bend, KS 67530

Phone: (620) 793-0832 Operator License #: 33153

Type of Well: Oil Well Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 03/06/07 (Date)

by: Pat Staab (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. (repeated for multiple formations)

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Rigged up and ran in with 2-3/8" mill and 65 jts tbg to 2000'. Cement with 100 sx 60/40 10% gel & 300# hulls. Tried to pull tbg & csg picked up. Got 5 jts tbg & cemented with 130 sx 60/40 10% gel-didn't circulate cement. Pull out 12 jts tbg & cement with 200 sx 60/40 10% gel & 200# hulls-didn't circulate cement. Pump 200 sx 60/40 10% gel & 600# hulls-didn't circulate cement. Pull 9 jts tbg-shut down. Ran in 9.5 jts tbg-hit tbg, pull .5jt-pump 75sx 60/40 10% gel 1/4# flo'seal with 300# hulls-circulated cement to surface. Pull out tbg & pressured up csg to 300#-top off with 25 sx 60/40 10% gel.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc. License #: 6901

Address: P.O. Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: Krier Oil Operations

State of Kansas County, Barton, ss.

Joseph F. Strube (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL Notary Public - State of Kansas My Appt. Expires 4/13/2010

(Signature) [Handwritten Signature] (Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED and SWORN TO before me this 15th day of March, 2007

[Handwritten Signature] My Commission Expires: 4/13/2010 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

009-21841-00-00

API Number: 15-00-21844

Lease Name: Lindholm

Well Number: #1

Spot Location (QQQQ): SW - NW - NW -

4290 Feet from North / South Section Line

4950 Feet from East / West Section Line

Sec. 28 Twp. 20 S. R. 13 East West

County: Barton

Date Well Completed: 05/13/1980

Plugging Commenced: 03/09/07

Plugging Completed: 03/13/07

RECEIVED KANSAS CORPORATION COMMISSION MAR 16 2007 CONSERVATION DIVISION WICHITA, KS

PKT

# ALLIED CEMENTING CO., INC.

30730

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Great Bend

DATE <u>3-13-07</u>	SEC <u>28</u>	TWP. <u>20</u>	RANGE <u>13</u>	CALLED OUT <u>11:00 AM</u>	ON LOCATION <u>12:00 PM</u>	JOB START <u>12:00 PM</u>	JOB FINISH <u>1:00 PM</u>
LEASE <u>Lindholm</u>	WELL # <u>1</u>	LOCATION <u>281 + Smile blktop 1 W, S</u>			COUNTY <u>Barton</u>	STATE <u>Ks</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)			E / side				

CONTRACTOR D.S. + W Well Serv.  
 TYPE OF JOB Old hole plug  
 HOLE SIZE 7.875"  
 CASING SIZE 4 1/2" DEPTH 300'  
 TUBING SIZE DEPTH 300'  
 DRILL PIPE DEPTH  
 TOOL DEPTH  
 PRES. MAX 300# PSI MINIMUM  
 MEAS. LINE SHOE JOINT  
 CEMENT LEFT IN CSG.  
 PERFS.  
 DISPLACEMENT Freshwater  
 EQUIPMENT  
 PUMP TRUCK CEMENTER Alk H.  
 # 120 HELPER Dwayne W.  
 BULK TRUCK  
 # 260 DRIVER Steve T.  
 BULK TRUCK  
 # DRIVER

OWNER Roger Krier / Krier oil operations

CEMENT  
 AMOUNT ORDERED 2000 cx 60/40 10% Gel  
4# Flo-seal  
300# Cotton seed Halls USED 100#

COMMON	<u>6000 lb</u>	@	<u>10.65</u>	<u>639.00</u>
POZMIX	<u>4000 lb</u>	@	<u>5.80</u>	<u>232.00</u>
GEL	<u>9 24#</u>	@		
CHLORIDE		@		
ASC		@		
Halls	<u>300#</u>	@	<u>25.50</u>	<u>76.50</u>
NO SEAL	<u>25#</u>	@	<u>2.00</u>	<u>50.00</u>
HANDLING	<u>2200 lb</u>	@	<u>1.90</u>	<u>418.00</u>
MILEAGE	<u>2200 lb</u>	@	<u>6 ml</u>	<u>240.00</u>
TOTAL				<u>1655.50</u>

REMARKS:

hooked to tubing mix 75 sx 60/40 10% gel  
4# Flo-seal start down pulled tubing out of  
hole pressure casing to 300# PSI w/ 25 sx  
60/40 10% Gel 4# Flo-seal Cement did  
Circulate shut in wash up + big down  
300# Halls in cement

CHARGE TO: Craig Biggs  
 STREET 3807 22ND St  
 CITY Great Bend STATE Ks ZIP 67530

SERVICE

DEPTH OF JOB	<u>300'</u>		
PUMP TRUCK CHARGE			<u>720.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>6</u>	@	<u>6.36</u> <u>38.00</u>
MANIFOLD		@	
TOTAL <u>756.00</u>			

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	<b>RECEIVED</b>
	@	KANSAS CORPORATION COMMISSION
	@	<b>MAR 16 2007</b>

CONSERVATION DIVISION  
WICHITA, KS

TAX \_\_\_\_\_  
 TOTAL CHARGE 2411.50  
 DISCOUNT 241.50 IF PAID IN 30 DAYS

SIGNATURE X Tully Jeffrey

X Tully Jeffrey  
 PRINTED NAME

# ALLIED CEMENTING CO., INC.

30588

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

*Heat Bend*

DATE <u>3-12-07</u>	SEC. <u>28</u>	TWP. <u>20</u>	RANGE <u>13</u>	CALLED OUT <u>7:00AM</u>	ON LOCATION <u>8:30AM</u>	JOB START <u>10:00AM</u>	JOB FINISH <u>3:00PM</u>
LEASEE <u>Lindhelm</u>		WELL # <u>1</u>	LOCATION <u>281 Hwy # 5 mile B top</u>			COUNTY <u>Barton</u>	STATE <u>Ka</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)		<u>1 west 1/4 south east into</u>					

CONTRACTOR D.S. & W  
 TYPE OF JOB Plug thru tubing  
 HOLE SIZE \_\_\_\_\_ T.D. 3443'  
 CASING SIZE 4 1/2 DEPTH 3442'  
 TUBING SIZE 2" DEPTH 2000'  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 500\* MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_

OWNER Krieger Oil Operations

CEMENT AMOUNT ORDERED 630.00 x 60/40 10% gel  
~~500~~ used 630.00 cement

COMMON	<u>378.00</u>	@	<u>10.65</u>	<u>4025.70</u>
POZMIX	<u>252.00</u>	@	<u>5.80</u>	<u>1461.60</u>
GEL	<u>54.00</u>	@	<u>16.65</u>	<u>899.10</u>
CHLORIDE		@		
ASC		@		
<u>Hulls</u>	<u>1100*</u>	@	<u>25.50</u>	<u>280.00</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>695.00</u>	@	<u>1.90</u>	<u>1320.50</u>
MILEAGE	<u>695.00</u>	@	<u>0.9</u>	<u>375.30</u>
TOTAL				<u>8362.20</u>

EQUIPMENT

UB  
 PUMP TRUCK CEMENTER J.D. Daehling  
 # 181 HELPER Kevin Davis  
 BULK TRUCK  
 # 260 DRIVER Don Dagen  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

KCC-WITNESSED - PAT STAAB  
1st 2000' - 100' AX W 300\* hulls  
2nd 2000' - circ w 130  
did not circulate 3' loaded 200.00  
1/4 10% gel w 200\* hulls, no circulation, 4th  
loaded 200.00 x 60/40 10% gel & mixed in 600\* hulls  
in cement. Cement did not circulate.

SERVICE

DEPTH OF JOB	<u>2000'</u>			
PUMP TRUCK CHARGE				<u>720.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>6</u>	@	<u>6.00</u>	<u>36.00</u>
MANIFOLD		@		
		@		
		@		

CHARGE TO: Krieger Oil Operations  
 STREET P.O. Box 763  
 CITY Heat Bend STATE Kansas ZIP 67530

*Thank you!*

TOTAL 756.00

RECEIVED  
KANSAS CORPORATION COMMISSION

PLUG & FLOAT EQUIPMENT

MAR 16 2007

	@			
	@			
	@			
	@			
	@			
	@			

TOTAL \_\_\_\_\_

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE

*X Roy Krieger*

PRINTED NAME

*X Thanks*