

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: W. D. Short Oil Co., LLC

Address: P. O. Box 729-102 S. River Rd., Oxford, Ks. 67119

Phone: (620) 455-3576 Operator License #: 33608

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 01-23-2007 (Date)

by: Barry Metz (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Mississippi Lime Depth to Top: 3360' Bottom: 3372' T.D. 3503'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-173-01630-000³

Lease Name: O.S.A. unit KCC PKT

Well Number: 15 319107
RBDMS

Spot Location (QQQQ): _____ - SE - SW - NE

2010 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 15 Twp. 29 S. R. 1 East West

County: Sedgwick

Date Well Completed: 03-26-1964

Plugging Commenced: 01-09-2007

Plugging Completed: 03-08-2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi Lime	Oil	3360'	3372'	8-5/8"	308'	0
				5-1/2"	3725'	2405'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 33310' w/2sx of cement, shot pipe off @ 2405', laid down pipe, set top plug w/ 60/40 Poz Mix w/4% Gel From 350' to Surface.

Name of Plugging Contractor: W. D. Short Oil Co., LLC License #: 33608

Address: P.O. Box 729 Oxford, Ks. 67119

Name of Party Responsible for Plugging Fees: W. D. Short Oil Co., LLC

State of Kansas County, Sumner, ss.

William D. (Don) Short, Jr.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 729, 102 S. River Rd. Oxford, Ks. 67119

DENESE A. WILSON
Notary Public - State of Kansas
My Appt. Expires 3-30-09

SUBSCRIBED and SWORN TO, before me this 13th day of March, 2007

[Signature] My Commission Expires: 3-30-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 15 2007
CONSERVATION DIVISION
WICHITA, KS

PKT

LOG-TECH
1011 240th Ave.
HAYS, KANSAS 67601
(785) 625-3858

Date 1-10-07

CHARGE TO: W.D. Short
 ADDRESS: PO Box 1 Oxford, Ks 67119-0001
 R/A SOURCE NO. _____ CUSTOMER ORDER NO. Verbal o/w
 LEASE AND WELL NO. OSA #15 FIELD _____
 NEAREST TOWN Clearwater COUNTY Seminole STATE Ks.
 SPOT LOCATION SE SW NE SEC. 15 TWP. 29S RANGE 1 West
 ZERO AGL CASING SIZE 5.5 WEIGHT _____
 CUSTOMER'S T.D. 3739 LOG TECH _____ FLUID LEVEL 350
 ENGINEER STAN LUENBERGER OPERATOR DAN MASKE

PERFORATING				
Description	No. Shots	From	Depth To	Amount

DEPTH AND OPERATIONS CHARGES					
Description	From	Depth To	Total No. Ft.	Price Per Ft.	Amount
<u>Set Cast Iron Bridge Plug #3310</u>	<u>0</u>	<u>3310</u>	<u>3310</u>	<u>Min</u>	<u>1000 00</u>
<u>5 1/2" Cast Iron Bridge Plug</u>					<u>800 00</u>

MISCELLANEOUS			
Description	Quantity	Amount	T.W.T.
<u>Service Charge</u>			
<u>T.J. 12:00</u>			
<u>A.O.L. 2:00</u>			
<u>S.J. 2:05</u>			
<u>F.J. 2:55</u>			
<u>Truck Rental #3</u>		<u>950 00</u>	

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 15 2007
 Sub Total 2790 00
 CONSERVATION DIVISION
 WICHITA, KS
 Tar _____
 _____ 30 DAYS
 _____ 2062 00

PRICES SUBJECT TO CORRECTION BY BILLING DEPARTMENT

RECEIVED THE ABOVE SERVICES ACCORDING TO THE TERMS AND CONDITIONS SPECIFIED ON THE REVERSE SIDE TO WHICH WE HEREBY AGREE.

Customer Signature W. Kenneth Short Date 1-10-07

Kivett Plugging & Pipe Pulling, Inc.

INVOICE

**P.O. Box 134
Blackwell, OK 74631-0134
(580) 363-3036**

Date	Invoice #
1/17/2007	01-1691-07

Bill To
Short Oil Co. P.O. Box 729 Oxford, KS 67119

Lease
OSA #15 SE SW NE 15-29S-1W Sedgwick County

FILE COPY

SCANNED

1-23-07 DATE

Terms
Net 30

Date	Description	Amount
1/9/2007	Furnish tools and supervision to P&A well. MIRU. Set anchors. Shut down for night.	
1/10/2007	Lay down rods and tubing. Dug out head and unpack. Waited on wire line truck. Set CIBP w/cmt 3310. Pull slips and work pipe. Shot pipe 2502--couldn't pull. Shot pipe 2405--pipe free. Shut down for night.	
1/11/2007	Lay down pipe--75 jts.--14#, RG2 Rig down and dug up anchors. Supervision Casing Tools Backhoe Cut pipe 2 times	500.00 750.00 350.00 700.00

Thank You!

<i>Thank you for your business.</i>	Total \$2,300.00 RECEIVED
-------------------------------------	--

KANSAS CORPORATION COMMISSION

MAR 15 2007

CONSERVATION DIVISION
WICHITA, KS



Roadrunner Well Service
 15 E Fifth, Suite #3000
 Tulsa, OK 74103

Invoice

Date	Invoice #
1/15/2007	682

Bill To
W.D. Short Oil Company 102 South River Rd P.O. Box 729 Oxford, Kansas 67119

P.O. No.	Terms	Project
O.S.A. #15		

Quantity	Description	Rate	Amount
	01/09/07 O.S.A. # 15 Sedgwick KS Arrive on location work rig into location and spot. RU rig. SDFTN		
4	Rig Time per hour	225.00	900.00
20	Fuel Charge	3.00	60.00
4	Insurance Charge	10.00	40.00
	01/10/07 O.S.A. #15 Sedgwick KS Safety meeting service rig. RU rod equipment. Un hang rods and unset pump. POOH w/ 3/4" rods and pump. RD rod equipment and RU Tbg equipment. RU on Tbg and release pkr. POOH w/ Tbg 2 3/8 105 jt and 130 rod total. Tie back and RU 5 1/2" csg. equipment. dig around well head wait on wire line unit. RU wire line unit and RIH w/ CIBP and set @ 3300'. POOH and RD unit. Unpack 5 1/2 csg and work from -0- to 90k. RU sick lines and RIH and blow csg @ 2502. Not free. Continue working csg. RBIH w/ slick line. SDFTN		
1	Crew Transportation per hour	150.00	150.00
1	Per Diem per day	240.00	240.00
8.5	Rig Time per hour	225.00	1,912.50
42.5	Fuel Charge	3.00	127.50
8.5	Insurance Charge	10.00	85.00
1	Tubing Tongs per day	175.00	175.00
	01/11/07 O.S. A. #15 Sedgwick		
		Total	RECEIVED

MAR 15 2007

CONSERVATION DIVISION
 WICHITA, KS

Roadrunner Well Service
 15 E Fifth, Suite #3000
 Tulsa, OK 74103

Invoice

Date	Invoice #
1/15/2007	682

Bill To
W.D. Short Oil Company 102 South River Rd P.O. Box 729 Oxford, Kansas 67119

P.O. No.	Terms	Project
O.S.A. #15		

Quantity	Description	Rate	Amount
	Safety meeting and service rig. RU csg tongs. POOH w/ 5 1/2 csg. Laying down having to clean slips and tongs dies a lot. Finish laying down csg 75 total 5 1/2 csg. RD csg equipment and RD rig and move out.		
1	Crew Transportation/Pickup per day	150.00	150.00
1	Per Diem per day	240.00	240.00
5	Rig Time per hour	225.00	1,125.00
25	Fuel Charge	3.00	75.00
5	Insurance Charge	10.00	50.00
	Out-of-state sale, exempt from sales tax	0.00%	0.00
		Total	RECEIVED 2000.00

MAR 15 2007

CONSERVATION DIVISION
 WICHITA, KS

CONSOLIDATED
OIL WELL
SERVICES, LLC

REMIT TO
Consolidated Oil Well Services, LLC
Dept. 1228
Denver, CO 80256

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE

Invoice # 212189

Invoice Date: 03/06/2007 Terms:

Page 1

W.D. SHORT OIL CO LLC
P.O. BOX 729
OXFORD KS 67115
() -

O.S.A. UNIT #15
16951
03-02-07

Part Number	Description	Qty	Unit Price	Total
1131	60/40 POZ MIX	105.00	9.8000	1029.00
1118A	S-5 GEL/ BENTONITE (50#)	360.00	.1500	54.00
Description		Hours	Unit Price	Total
436	80 BBL VACUUM TRUCK (CEMENT)	3.00	90.00	270.00
439	TON MILEAGE DELIVERY	292.50	1.10	321.75
485	P & A OLD WELL	1.00	550.00	550.00
485	EQUIPMENT MILEAGE (ONE WAY)	65.00	3.30	214.50

Parts:	1083.00	Freight:	.00	Tax:	79.06	AR	2518.31
Labor:	.00	Misc:	.00	Total:	2518.31		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed _____

Date _____

RECEIVED
KANSAS CORPORATION COMMISSIO

BARTLESVILLE, OK
278 CR 2706 74003
918/338-0808

EUREKA, KS
820 E. 7th 67045
620/583-7664

OTTAWA, KS
2631 So. Eisenhower Ave. 66067
785/242-4044

GILLETTE, WY
300 Enterprise Avenue 82716
307/686-4914

THAYER, KS
8655 Dorn Road 66776
620/839-5269

WORLD
837 Hwy US 16 E 62401
307/347-4577
MAR 15 2007
CONSERVATION DIVISION
WICHITA, KS

