

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

Amerdel

19181-00-00

Lease Operator: American Warrior Inc.

Address: P.O Box 399, Garden City Ks. 67846

Phone: (620) 272-1023 Operator License #: 4058

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 7/25/06 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Arbuckle Depth to Top: 3209' Bottom: 3219 T.D. 3219

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-167-00300

Lease Name: Hall

Well Number: #1

Spot Location (QQQQ): C - NW - SW - SE
990' Feet from North / South Section Line

2310' Feet from East / West Section Line

Sec. 36 Twp. 14S S. R. 15 East West

County: Russell

Date Well Completed: 1936

Plugging Commenced: 2/22/07

Plugging Completed: 2/22/07

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|-------|------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| Arbuckle | oil. | surface | 810' | 85/8 | 810' | 0 |
| | | surface | 3210' | 51/2 | 3210' | 0 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log Tech perf 1400', 810' 2spf. Ran tbg to 1400'. Swift hooked up to tbg. Mixed and pumped 100 sx 60/40 pos cement with 300# hulls.

Pulled tbg. Swift hooked up to 85/8. Mixed and pumped 20sx 60/40 pos. Swift hooked up to 51/2 casing. Mixed and pumped 55sx 60/40 pos cement with 100# hulls. Cut Casings off 6' Below surface, Capped. Back filled.

express well service + supply inc

Name of Plugging Contractor: Swift Services inc License #: 32382 @ 6426


Address: P.O. box 466 Ness City Kansas 67560

*KCC PKT 3/19/07
per CP2/3*

Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Kansas County, Finney, ss.

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) *[Signature]*

(Address) P.O. Box 399 Garden City Kansas 67846

SUBSCRIBED and SWORN TO before me this 22 day of February 20 07

[Signature] My Commission Expires: 09/22/09
Notary Public

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 15 2007
CONSERVATION DIVISION
WICHITA, KS