

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: BEREN, CORP.

Address: PO BOX 723 HAYS, KS 67601

Phone: (785) 628-6101 Operator License #: 5364

Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2-22-07 (Date)

by: RICH WILLIAMS (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

L-KC (B) Depth to Top: 3557 Bottom: 60 T.D. 3800'

L-KD (G) Depth to Top: 3599 Bottom: 3603 T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-01725-00-00

Lease Name: J.L. BALTHAZOR KCC PKT 3/19/07

Well Number: 2 per oper - SHANNA

Spot Location (QQQQ): NW - NW - NE -

4950 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 19 Twp. 9 S. R. 20 East West

County: ROOKS KCC PKT

Date Well Completed: 8-11-51 3/19/07

Plugging Commenced: 2-22-07 per RB Dms

Plugging Completed: 2-26-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
L-KC (B&G)	OIL	0	187'	8-5/8	8-11-51	---
		0	3794'	5-1/2 14#&15.5#	8-11-51	----

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RUN TBG OPEN END TO 3750', MIX 50 SKS W/ 100# HULLS. PULL TUBGING UP TO 3121' MIX 100SKS W/ 200# HULLS

PULL UP TO 1800', MIX 150 SKS W/ 300# HULLS. PULL UP TO 900', MIX 75 SKS W/ 100# HULLS. CIR CMT

PULL REST OF TBG TOP OFF W/ 10 SKS. HOOK UP TO 8-5/8 PRESS TO 500# NO CMT FULL. DONE

USED 350 SKS 60/40 POS 10% GEL AND 700# OF HULLS

Name of Plugging Contractor: BEREXCO, INC. License #: 5363

Address: PO BOX 723 HAYS, KS 67601


Name of Party Responsible for Plugging Fees: GURT GABEL Beren, Corp KCC PKT per oper - SHANNA

State of KS County, ELLIS, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gurt Gabel

(Address) PO BOX 723 HAYS, KS 67601



SUBSCRIBED and SWORN TO before me this 6 day of MARCH, 20 07

Shanna Miller My Commission Expires: 9-19-09
Notary Public

RECEIVED

MAR 14 2007

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA