

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: John O. Farmer, Inc.

Address: P.O. Box 352, Russell, KS 67665

Phone: (785) 483-3144 Operator License #: 5135

Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 167-23,391-00-00

Lease Name: Mabb "B"

Well Number: #1

Spot Location (QQQQ): 75' S - SW - NE - SW
1575 Feet from ☐ North / ☒ South Section Line

1650 Feet from ☐ East / ☒ West Section Line

Sec. 6 Twp. 14 S. R. 14 ☐ East ☒ West

County: Russell

Date Well Completed: 11-20-06

Plugging Commenced: 11:00 A.M., 3-5-07

Plugging Completed: 1:30 P.M., 3-5-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	483' @ 493'	-0-
(well never produced)				5-1/2"	3035'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st plug @ 2900' w/100 sks. cement & 300# hulls; 2nd plug @ 1600' w/100 sks. cement & 200# hulls. Cement circulated.

Mixed 20 sks. cement down 5-1/2" casing - shut in @ 400 PSI. Mixed 130 sks. cement down backside w/200# hulls - shut in @ 450 PSI.

TOTAL: 350 sks. 60/40 Pozmix, 10% gel w/1/4# flo-seal per sack & 700# hulls

Name of Plugging Contractor: Allied Cementing Company, Inc.

License #: 99996

Address: P.O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.

State of Kansas County, Russell, ss.

John O. Farmer III

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 13th day of March, 20 07

Margaret A. Schulte
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT KCC 3/19/07

RECEIVED

MAR 14 2007

KCC WICHITA

PKT

ALLIED CEMENTING CO., INC.

33081

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

COPY

DATE <i>3-5-07</i>	SEC. <i>6</i>	TWP. <i>14</i>	RANGE <i>14</i>	CALLED OUT	ON LOCATION <i>10:30 am</i>	JOB START <i>11:00 am</i>	JOB FINISH <i>1:30 pm</i>
LEASE <i>Maab</i>	WELL # <i>1</i>	LOCATION <i>1/2 S Balta + T-70 1/4 E N. into</i>			COUNTY <i>Russell</i>	STATE <i>KS</i>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR *L+M*
 TYPE OF JOB *Old Hole Plug*
 HOLE SIZE _____ T.D. *2900'*
 CASING SIZE *5/2* DEPTH _____
 TUBING SIZE *2 1/2* DEPTH _____
 DRILL PIPE DEPTH _____
 TOOL DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

EQUIPMENT

PUMP TRUCK CEMENTER *Craig*
 # *409* HELPER *Adrian*
 BULK TRUCK
 # *396* DRIVER *Brandon*
 BULK TRUCK
 # _____ DRIVER _____

REMARKS:

1st 2900 100% 300 Hauls.
2nd 1600 100% 200 Hauls. Cement Circulate.
Mix 20% down 5/2 - Shut in 400 psi.
Mix 130% down Backs. & w/ 200 Hauls
Shut in 450 psi.

Thank!

CHARGE TO: *JO Farmer*
 STREET _____
 CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE *Willie*

OWNER

CEMENT

AMOUNT ORDERED *400 60/40 10% Gel 1/4" Flt*
1000# Hauls

COMMON	<i>210</i>	@	<i>105</i>	<i>2236.50</i>
POZMIX	<i>140</i>	@	<i>5.80</i>	<i>812.00</i>
GEL	<i>25</i>	@	<i>16.65</i>	<i>416.25</i>
CHLORIDE		@		
ASC		@		
<i>Hauls</i>	<i>7</i>	@	<i>25.50</i>	<i>178.50</i>
		@		
		@		
		@		
		@		
		@		
HANDLING	<i>438</i>	@	<i>1.90</i>	<i>832.25</i>
MILEAGE	<i>94/sk/mile</i>			<i>240.00</i>
TOTAL				<i>4715.45</i>

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<i>720.00</i>
EXTRA FOOTAGE	@		
MILEAGE	<i>5</i>	@	<i>6.00</i> <i>30.00</i>
MANIFOLD	@		
	@		
	@		
TOTAL			<i>750.00</i>

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	
TOTAL		

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME

RECEIVED

MAR 14 2007

KCC WICHITA