

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Pickrell Drilling Company, Inc.
Address: 100 S. Main, Suite 505, Wichita, Kansas 67202
Phone: (316) 262-8427 Operator License #: 5123
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12-02-05 (Date)
by: Michael Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Cherokee Sd Depth to Top: 4049 Bottom: 4072 T.D. 4119

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-30274-00-00 ^{1 KCC}
Lease Name: Starrett "B" ^{afB}
Well Number: 1 ³⁻²¹⁻⁰⁷
Spot Location (QQQQ): _____ - C - SW - NE
1980 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 12 Twp. 17 S. R. 21 East West
County: Ness
Date Well Completed: 12-15-66
Plugging Commenced: 12-02-05
Plugging Completed: 12-02-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	400	None
				5 1/2	4111	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Pressured 8 5/8 x 5 1/2 Braden Head to 500#. PBTD 4079, Perfs. 4052-4055, CIBP 4100, 125 sx. cement squeeze of holes @ 3468-3499, 200 sx cement squeeze of holes @ 1721-1971, 155 sx. cement w/ 200# of hulls circulate from 1600 ft. to surface thru 2 3/8" tubing inside 5 1/2" csg., POOH w/ tbg., top off well w/ 20 sx.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382
Address: P.O. Box 466, Ness City, Kansas 67560-0466
Name of Party Responsible for Plugging Fees: Pickrell Drilling Company, Inc.
State of Kansas County, Sedgwick, ss.

RECEIVED
DEC 14 2005
12-14-05
KCC WICHITA

Jack Gurley (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jack Gurley
(Address) 100 S. Main, Suite 505, Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 13th day of December, 20 05
Karen A. Mans McGee My Commission Expires: 6-23-08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bem