

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado De-by Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20291-00-00

LEASE NAME Hayden

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 5 TWP. 9S RGE. 19 (XXX)(X)

COUNTY Rooks

Date Well Completed

Plugging Commenced 1-8-96

Plugging Completed 1-10-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P.O. Box 21468 Tulsa, Oklahoma 74121-1468

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)
by Dennis Hammel (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3536

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 209' | none |
| | | | | 5 1/2" | 3535' | 835' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Dumped 5 sacks cement on CIBP at 2975'. Shot casing at 2025'. Pulled to 1950'; pumped 200# hulls and 140 sacks cement. Casing hung up. Shot pipe at 1700'. and 1250'. pumped 35 sacks cement. Shot pipe at 750'. pulled one joint, pumped 200# hulls and 50 sacks cement. Pulled to 350' circulated cement with 45 sacks cement and 200# hulls. Pulled rest of casing. (60/40 10% gel). Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company Tulsa, Ok. 74121

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 18th day of January, 19 96

Irene Herzaerg
Notary Public

My Commission Expires:
USE ONLY ONE SIDE OF EACH FORM

