

15-163-01581-00-01

LEASE NAME JELINEK 3

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #3

LEASE OPERATOR Venture Resources, Inc.

ADDRESS 518 17th. St. Ste. 1130 Denver, CO 80202

PHONE# (303) 573-6634 OPERATORS LICENSE NO. 3252

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

3960' Ft. from S Section Line

660' Ft. from E Section Line

SEC. 30 TWP. 9S RGE. 18 NE1/4 (W)

COUNTY Rooks

Date Well Completed 6-24-53

Plugging Commenced 12-15-95

Plugging Completed 12-15-95

The plugging proposal was approved on October 31, 1995 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Toronto/Kansas City Depth to Top 3347' Bottom 3536' T.D. PBTID 3564'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	155'	8 5/8"	155'	NONE
		Surface	3677'	5 1/2"	3677' 3669'	NONE
					6224'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s Perf. 2 holes @ 2030', 1560', & 950'. Run tubing in to 3004', spotted 50 Sks. Cement on bottom w/200#'s hulls. Spotted 30 sks. cement @ 2048', spotted 20 sks. cement @ 1580'. Circulated cement from 959' used 100 sks. to get circulation. Used 10 sks. of gel as spacer between plugs. mixed 100 hulls in plug @ 2048' & 200 #'s hulls @ 959. Pull tubing & hook up to 5 1/2" Pumped 75sks. down casing 600#'s-max. 250#'s Shut in. Hooked up to 8 5/8" pressure 400#'s could not pump into. Total cement used 275 sks. 60/40 w/10% gel. Plug down @ 2:30PM 12-15-95.

Name of Plugging Contractor Allied Cementing License No.

Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Venture Resources

STATE OF Colorado COUNTY OF Denver

Robert E. Plante

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of Jan., 19 96

Notary Public

My Commission Expires: 4/4/99

USE ONLY ONE SIDE OF EACH FORM

