

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-163-01585-00-01

API NUMBER E-16,521

LEASE NAME Sollenberger

WELL NUMBER 3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 30 TWP. 9 RGE. 18 (X) or (W)

COUNTY Rooks

Date Well Completed

Plugging Commenced 12.30.88

Plugging Completed 12.30.88

RECEIVED
 STATE CORPORATION COMMISSION
 1/16/89
 JAN 6 1989
 CONSERVATION DIVISION
 Wichita, Kansas

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR William E. Hammerschmidt

ADDRESS 904 S. Section Line Plainville, Mo

PHONE# (913) 434-2403 OPERATORS LICENSE NO. 8133

Character of Well S.W.D.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? KCC - Hays, KS.

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation S.W.D. Depth to Top Bottom T.D. 3635

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
5 1/2" casing set at 3612' w/100 SKS. O.H at 3612' - 35'. Base Dakota at 487'.
Sq. at 950-1150 w/250 SKS (1956). Ordered 250 SKS (65/35 Poz 10%)
Get with 1/4 EC Plus 6 SKS Nells. (Plus 50 SKS common). Pumped 50
SKS common w/1/4 EC plus pumped in 5 1/2 casing 175 SKS cement
 (If additional description is necessary, use BACK of this form.) over

Name of Plugging Contractor Allied Cement License No.

Address P.O. Box 31 Russell


STATE OF Kansas COUNTY OF Russell, ss.

William E. Hammerschmidt (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William E. Hammerschmidt

(Address) 904 South Sec. Line

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 89


 My Commission Expires

Eleanor L. Wilson
 Notary Public

w 1/4 # F.C. Max 800 # S.I 500 # psi. Pumped in 8 5/8" casing
75 SKs. Cement w 1/4 # F.C. plus Hulls mixed in cement.

Max 800 # S.I. 500 # psi.