


15-163-02865-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec. 5 Twp. 9 Rge. (E) 19 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE NE SE
Lease Owner Westgate-Greenland Oil Company
Lease Name Carrow Well No. 1
Office Address 1022 Union National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 10, 1949 19
Application for plugging filed November 10, 1949, orally 19
Application for plugging approved November 10, 1949, orally 19
Plugging commenced November 10, 1949 19
Plugging completed November 10, 1949 19
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	167	9 5/8"	167	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3508 to 160 feet
Set plug at 160 feet and dumped 20 sacks cement to 85 feet
Filled with heavy mud from 85 feet to 30 feet and
Run 10 sacks cement to cellar base.

11/17/49

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company Attn: G. E. Bitler
Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler
1022 Union Natl Bk Bldg, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of November, 19 49
Esther Russell
Notary Public.

My commission expires May 25, 1953



COMPANY: Westgate Greenland Oil Co.
 CONTRACTOR: Jackson Drilling Corp.
 FARM: Cerrow #1
 LOCATION: NE NE SE Section 5-9-19W
 Rooks County, Kansas
 COMMENCED: October 30, 1949
 COMPLETED: November 10, 1949

0	to	860	Shale & shells
860	to	925	Pyritic shale
925	to	1170	Sand
1170	to	1445	Shale & Red bed
1445	to	1480	Anhydrite
1480	to	1870	Shale & shells
1870	to	2310	Shale & lime
2310	to	2375	Lime
2375	to	2490	Lime & shale
2490	to	2610	Shale
2610	to	2880	Shale & lime
2880	to	2930	Shale
2930	to	3030	Lime & shale
3030	to	3243	Lime
3243	to	3290	Lime & shale
3290	to	3345	Lime
3345	to	3400	Lime & shale
3400	to	3445	Lime
3445	to	3476	Lime & shale
3476	to	3484	Simpson
3484	to	3508	Arbuckle
		3508 T.D.	

9 5/8" - 40# casing set at 167 feet - Cemented with 110 sacks cement.

Dry and abandoned

Measurements from top of derrick floor

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Cerrow #1, Section 5-9-19W, Rooks County, Kansas, as reflected by files of the Jackson Drilling Corporation.

Clare A. Stewart
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas this 18th day of November 1949

Dorothy J. Wilson
 Dorothy J. Wilson

My Commission expires November 30, 1950

RECEIVED
 NOV 22 1949
 STATE OF KANSAS
 COMMISSION

PLUGGING
 FILE SEC 5-9-19W
 BOOK PAGE 184 LINE 43