

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION Form CP-4
10/12/82
OCT 12 1982
Rev. 12-15-80

CONSERVATION DIVISION
Wichita, Kansas

15-163-21599-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rooks SEC. 5 TWP. 9 RGE. 19 E/W
Location as in quarters or footage from lines:
C/NW/SE

Locate Well
correctly on above
Section Platt.

Lease Owner Frontier Oil Company
Lease Name Cerrow "B" Well No. #1
Office Address 1437 N. Franklin - Russell, Ks. 67665
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed _____
Application for plugging filed _____
Plugging commenced September 16, 1982
Plugging completed September 27, 1982
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor

Producing formation _____ Depth to top _____ bottom _____ T.D. 3478'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	264'	NONE
				4 1/2"	3476'	2027.63'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 3300' and four (4) sacks cement.
Shot pipe @ 2500', 2200' and 2000'.
Pulled fifty-one (51) joints 4 1/2" casing.
Squeezed well with five (5) sacks hulls, ten (10) sacks gel, seventy (70) sacks cement, ten (10) sacks gel, one (1) sack hulls, released plug and pumped seventy (70) sacks 50/50 pozmix cement with 6% added gel. Had 100 psi shut in pressure..

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
JAMES W. ROCKHOLD - Box 698 - Great Bend,
(Address) Ks. 67530

SUBSCRIBED AND SWORN TO before me this 8th day of October, 1982

My Commission expires:



Margaret Prosser
Notary Public.