

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

ROOKS County. Sec. 5 Twp. 9 Rge. 19 (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SW NE

Lease Owner B & R DRILLING, INC.

Lease Name OUDRESEK Well No. 1

Office Address RUSSELL, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 9/28 1947

Application for plugging filed 9/28 1947

Application for plugging approved 9/28 1947

Plugging commenced 9/28 1947

Plugging completed 9/28 1947

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? YES

Name of Conservation Agent who supervised plugging of this well.

Producing formation Depth to top Bottom Total Depth of Well 3541 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	182'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

GUNNED PITS - FILLED TO 186' WITH HEAVY MUD - PLUG AND 15 SACKS CEMENT - HEAVY MUD TO 25' - PLUG AND 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R DRILLING, INC.
Address RUSSELL, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

C. L. ROBERTS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
RUSSELL, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 2ND day of OCTOBER, 1947

My commission expires 6/17/50 Notary Public.

FILED OCT 5 9 1947
RUSSELL 136 LINE 33

10/6/47

15-163-30338-00-00

B & R DRILLING, INC.
OUDRESEK #1

SEC. 5 TWP. 9 RGE. 19
COUNTY: ROOKS, KANSAS

TOTAL DEPTH: 3541'
COMM: 9/15/47 COMP: 9/28/47

TOP TOPEKA - 3008'
" HEEBNER - 3211
" LANSING - 3235
" SIMPSON - 3501
" ARBUCKLE - 3507

CASING
9 Jts. 8 5/8" SET AT 182'

CEMENT
165 SX-CEMENT CIRCULATED

FORMATION:	DEPTH:
SAND & SHALE	140'
SHALE & SHELLS	285
SHALE	470
SHALE & SHELLS	540
SAND	660
SHALE & SAND	730
IRON & SHALE	900
SAND, SHELLS, & SHALE	1028
SAND	1210
SHALE & SHELLS	1493
ANHYDRITE	1560
RED BED & SHALE	1615
SHALE & LIME	1955
LIME	2060
LIME & SHALE	2865
LIME	3520
ARBUCKLE	3541

STATE OF KANSAS)
) SS
RUSSELL COUNTY)

I HEREBY CERTIFY THAT THE ABOVE INFORMATION IS TRUE
AND CORRECT TO THE BEST OF MY KNOWLEDGE.

[Signature]

SUBSCRIBED AND SWORN TO BEFORE ME THIS 29TH DAY OF SEPTEMBER, 1947.

[Signature]
NOTARY PUBLIC

MY COMM. EXPIRES 6/17/50

10/6/47

5 9 19W
126 33



STATE OF KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 800 BITTING BUILDING
 WICHITA, KANSAS

October 2, 1947

IN REPLY PLEASE
 REFER TO THIS
 SUBJECT

B & R Drilling Co.
 Russell, Kansas

Gentlemen:

IN ACCOUNT WITH Conservation Division, State Corporation Commission
 Wichita, Kansas

WE Charge YOU

Plugging Assessment.....\$ 25.00

Well No. 1
 Farm Oudrasek
 Description SW SW NE 5-9-19W
 County Rocks
 File: 136-33

The assessment for the plugging of all wells in the State of Kansas is one cent per foot, with a maximum of \$25.00 and a minimum of \$5.00.

This assessment will be past due October 30, 1947

PLEASE RETURN ONE COPY WITH REMITTANCE

NOTE: We also need a written Application, Well Log and Well Plugging Record on this well to complete our file.

**760*
David
10-17-47
JB