


15-163-00196-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 30 Twp. 9 Rge. 18 (E) (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE SE NW
Lease Owner Anschutz Drilling Company, Inc.
Lease Name Hilgers Well No. 1
Office Address 612 Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-9 19 49
Application for plugging filed via telephone 10-9 19 49
Application for plugging approved via telephone 10-9 19 49
Plugging commenced 10-9 19 49
Plugging completed 10-9 19 49
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3660 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	205'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug 200 ft. cemented with 15 sacks Portland cement through drill pipe
Top Plug 30 ft. cemented with 10 sacks Portland cement through drill pipe

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anschutz Drilling Company, Inc.
Address 612 Union National Bank Bldg., Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
H. R. Jensen (employee of owner) or (owner and operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Jensen
612 Union Nat'l Bk Bldg., Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 1949

My commission expires September 12, 1953

22-5133-s 9-48-10M



Marche Doye Notary Public

Received 10/12/49

WELL LOG

HILGERS #1, 30-9-18, SE SE NW

Rooks County, Kansas

0	205	Surface clay
205	620	Shale
620	1170	Shale, sand, shells
1170	1565	Shale and shells
1565	1605	Anhydrite
1605	1615	Shale and shells
1615	1900	Shale and shells
1900	2115	Shale and shells
2115	2315	Shale and shells
2315	2415	Lime and shale
2415	2500	Lime and shale
2500	2615	Lime and shale
2615	2715	Lime and shale
2715	2785	Lime and shale
2785	2835	Lime and shale
2835	2935	Lime and shale
2935	3035	Lime and shale
3035	3125	Lime and shale
3125	3175	Lime
3175	3235	Lime
3235	3290	Lime
3290	3337	Lime
3337	3375	Lime and shale
3375	3410	Lime and shale
3410	3445	Lime and shale
3445	3475	Lime
3475	3500	Lime and shale
3500	3535	Lime and shale
3535	3585	Lime
3585	3605	Lime
3605	3625	Lime
3625	3631	Lime
3631	3650	Arbuckle Lime
3650	3660	Lime
3660		Rotary Total Depth

COMMENCED: 9-28-49

COMPLETED: 10-9-49

Elev. 2191 DF

RECEIVED
 Conservation
 10/12/49
 STATE CORPORATE
 COMMISSION
 KANSAS

CASING RECORD:

Set 8-5/8" surface casing at 205',
 cemented with 125 sacks cement by
 Sun Oilwell Cementing Co.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Hilgers #1, SE SE NW 30-9-18, Rooks County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

By: *H. R. Jensen*
 H. R. Jensen
 Assistant Secretary

Subscribed and sworn to before me, a Notary Public, this 12th day of October, 1949.

Martha Long
 Notary Public

My commission expires September 12, 1953

PLUGGING
 FEET SEC—T—R—
 ROCK PAGE—LINE—