

15-163-01577-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rooks SEC. 30 TWP. 9S RGE. 18 ~~XX~~
Location as in quarters or footage from lines:
SW SW NW

Lease Owner Ladd Petroleum Corporation
Lease Name Hilgers Well No. 1
Office Address Box 520 Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 10-17-50
Application for plugging filed 2-17-83
Plugging commenced 5-25-83
Plugging completed 5-25-83
Reason for abandonment of well or producing formation Non-Commercial

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation LKC-ARB Depth to top 3280 bottom 3621 T.D. 3621
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		Surface	154'	8 5/8	154'	None
		Surface	3619'	5 1/2	3619'	None


Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set. Pump cement down Annulus, 125 sx 50-50 pozmix,
6% gel., 3% C.C., 1 1/2 sx Hulls, 400# max, pump 325 sx 50-50 pozmix, 6% gel, 3% C.C.,
7 1/2 sx hulls, 15 sx gel, 1 sx flocele down casing, 600# max. press.

NOTE: Well was squeezed @ 450' in 1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF Kansas COUNTY OF Rooks, ss.
Warren Irwin (employee of owner) or (~~owner or operator~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



(Signature) Warren Irwin
Box 520, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1983
Howard D. Ewert
Notary Public.

My Commission expires: 12-15-84

RECEIVED
STATE CORPORATION COMMISSION
6/1/83
JUN 01 1983