

15-163-19289-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 30 Twp. 9S Rge. 18 (E) (W)

Location as "NE/CNW/SW" or footage from lines W/2 SE/4 NE/4

Lease Owner Heathman-Seeligson Drilling Co.

Lease Name Jelinek Well No. 5

Office Address 254 No. Washington, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-6-54 1954

Application for plugging filed 9-6-54 1954

Application for plugging approved 9-6-54 1954

Plugging commenced 9-6-54 1954

Plugging completed 9-6-54 1954

Reason for abandonment of well or producing formation Dry and Abandoned

If a producing well is abandoned, date of last production --- 19---

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elden Petty, Hays, Kansas

Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3629 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" 22.7#		none
				Spiralweld surf.		
				csg. cemented @ 160'		
				w/ 100 sacks cement		
				and 1 CC		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud. Bottom plug set at 155' with 1/2 sacks hulls and 15 sacks cement. Filled hole to 40'. Set top plug with 1/2 sacks hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Heathman-Seeligson Drilling Co.

Address 254 No. Washington, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

H. D. Shreve

(employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. HEATHMAN-SEELIGSON DRILLING CO.

(Signature) [Signature]

254 No. Washington, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of September, 1954

My commission expires June 28, 1956

D. Marjorie Matt
Notary Public.

PLUGGING
PLK SEC 30 T 9 R 18W
BOOK PAGE 62 LINE 39

9/10/54

DRILLERS' LOG

NAME: #5 JELINEK DATE SPUDDED: 8-28-54
 LOCATION: W/2 SE/4 NE/4 Sec. 30-9S-18W ROTARY COMPLETION: 9-6-54
 Rooks County, Kansas
 OPERATOR: Heathman-Seeligson Drilling Co. ELEVATION: 2187 DF
 2185 Gr
 2190 KB
 CONTRACTOR: Heathman-Seeligson Drilling Co. Rotary TOTAL DEPTH: 3629'
 SURFACE CASING: 8 5/8" 22.7# Spiralweld
 cemented at 160' w/100 sacks
 cement and 1 sack Calcium Chloride.
 Cement circulated.
 OIL STRING: None run - Dry and abandoned 9-6-54

GEOLOGICAL TOPS (KB)

Anhydrite	1528 (-652)
Heebner	3332 (-1142)
Lansing	3373 (-1183)
Arbuckle	3613 (-1423)
R.T.D.	3629 (-1439)

L O G

(Figures indicate bottom of formation)


Shale & Sand	0 to 40
Shale & Shells	160
Shale, Sand & Shells	855
Sand	918
Shale, Shells & Sand	1042
Sand	1280
Shale, Shells, Red Bed	1538
Anhydrite	1585
Shale & Shells	1895
Shale, Shells & Lime	2375
Lime & Shale	3265
Lime	3629
R.T.D.	3629

The undersigned, H. D. Shreve, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

HEATHMAN-SEELIGSON DRILLING CO.

By: 

Subscribed and sworn to before
 me, this 8th day of September, 1954.


 Notary Public

My commission expires: June 28, 1956.

