


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rooks County. Sec. 30 Twp. 9 Rge. 18 ~~XX~~/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
SE SW NE

Lease Owner OIL Property Management, Inc.  
Lease Name S & F Jelinek Well No. 2  
Office Address 300 Insurance Building, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plat

Dry Hole  
Date Well completed September 15 19 77  
Application for plugging filed September 15 19 77  
Application for plugging approved September 15 19 77  
Plugging commenced September 15 19 77  
Plugging completed September 15 19 77  
Reason for abandonment of well or producing formation \_\_\_\_\_  
Dry Hole

If a producing well is abandoned, date of last production 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3655  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole full of heavy mud to 660' w/70 sacks 50/50 Pozmix 6% Gel thru drill pipe  
Mud to 240' w/20 sacks 50/50 Pozmix, 6% Gel thru drill pipe  
Mud to 40' w/ $\frac{1}{2}$  sack hulls plug and 10 sacks cement

9/20/77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.  
Larry Curtis (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis  
Box 823, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of September, 19 77

My commission expires April 11, 1978

Alvordy M. Nague  
Notary Public.

DRILLERS' WELL LOG

DATE COMMENCED: September 6, 1977  
 DATE COMPLETED: September 15, 1977

Oil Property Management, Inc.  
 J & F JELINEK # 2  
 3E SW NE  
 Sec 30-T9-R1SW  
 Rocks County, Kansas

ELEVATION: 2191 K.B.

0 - 250' Shale, Post Rock  
 250 - 1270' Shale and Sand  
 1270 - 1557' Red Bed  
 1557 - 1597' Anhydrite  
 1597 - 1914' Shale  
 1914 - 2750' Shale and Lime  
 2750 - 3111' Lime and Shale  
 3111 - 3322' Lime  
 3322 - 3326' Shale  
 3326 - 3363' Lime  
 3363 - 3606' Lime and Shale  
 3606 - 3655' Dolomite  
 3655' RFD

FORMATION TOPS

Anhydrite	1557
Topoka	3111
Heebner	3322
Toronto	3348
Lansing	3363
Arbuckle	3606
RFD	3655

SURFACE PIPES:

Set used 8 5/8", 28# pipe  
 at 299' w/175 sacks Common,  
 2% Gel, 3/4 ca. cl.

AFFIDAVIT

STATE OF KANSAS )  
 COUNTY OF BARTON ) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 19th day of September, 1977.

Alceste M. Hague  
 Notary Public

My Commission Expires: April 11, 1978

9/20/77