


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rocks _____ County. Sec. 31 Twp. 9 Rge. 18 (E) _____ (W) _____
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$
Lease Owner Barnett Drilling, Inc., Peel-Hardman & Shallow-Water
Lease Name Baumgartner Well No. 1
Office Address 117 First Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 31 19 50
Application for plugging filed December 31 19 50
Application for plugging approved December 31 19 50
Plugging commenced December 31 19 50
Plugging completed December 31 19 50
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3760 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Casing				8 5/8"	182'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 3760 feet to 180 feet. Set wooden plug at 180 feet and filled surface casing with 1 sack of hulls and 15 sacks of cement to 133 feet. Filled surface casing with heavy mud from 133 feet to 35 feet. Set wooden plug at 35 feet and filled casing with 1/2 sack of hulls and 10 sacks of cement to bottom of cellar.

RECEIVED
STATE CORP
1/13/51
JAN 13 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Barnett Drilling, Inc.
Address 117 First Nat'l. Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Hunter (employee of owner) or owner or operator of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Hunter
First Nat'l. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of January, 1951

Adelaide Olivier
Notary Public.

My commission expires May 12, 1951.

PLUGGING
FILE SEC 31 9 R 18
BOOK PAGE 53 LINE 8

BARNETT DRILLING, INC., PEEL-HARDMAN ANDTHE SHALLOW WATER REFINING COMPANYLOG OF BAUMGARTNER WELL NO. 1NE $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$ SECTION 31-9S-18W, ROOKS COUNTY, KANSAS

COMMENCED: DECEMBER 17, 1950.

COMPLETED: DECEMBER 31, 1950.

FORMATION	FROM	TO	REMARKS
Surface Clay	-0-	20	
Shale	20	65	
Sand and Gravel	65	110	
Shale	110	182	Set 8 5/8" Surface Casing at 182 feet, cemented with 125 sacks of cement.
Shale and Shells	182	1030	
Shale	1030	1050	
Sand	1050	1300	
Red Bed and Shale	1300	1560	
Red Bed	1560	1619	
Anhydrite	1619	1647	
Shale and Shells	1647	1770	
Shale, Shells and Lime	1770	2100	
Lime and Shale	2100	2425	
Shale	2425	2565	
Lime and Shale	2565	3145	
Lime	3145	3200	
Lime and Shale	3200	3275	
Lime	3275	3320	
Lime and Shale	3320	3336	
Lime	3336	3370	
Lime and Shale	3370	3408	
Lime	3408	3450	
Shale and Lime	3450	3495	
Lime	3495	3600	
Conglomerate and Lime	3600	3644	
Lime	3644	3664	
Cherty Lime	3664	3701	
Lime	3701	3708	
Conglomerate and Lime	3708	3725	
Shale and Lime	3725	3745	
Lime	3745	3760	
Total Depth		3760	Dry and Abandoned.

RECEIVED
 COMMISSION
 1/13/51
 JAN 13 1951
 DIVISION
 Wichita, Kansas

Certificate

I, W. R. Hunter, Vice-President of Barnett Drilling, Inc., hereby certify that to the best of my knowledge and belief the above is a true and correct log of the Baumgartner Well No. 1, located in the NE $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$ of Section 31-9S-18W, Rooks County, Kansas.

W. R. Hunter

Subscribed and sworn to before me, a Notary Public, in and for the County of Sedgwick, State of Kansas, this 9th day of January, 1951.

Adelaide Oliver
 Notary Public.

My commission expires May 12, 1951.

PLUGGING
 FILE SEC 31 T 9 R 18W
 BOOK PAGE 53 LINE 8