

15-163-00734-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

ROOKS County. Sec. 31 Twp. 9 Rge. 18 (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE NE NE

Lease Owner. B & R DRILLING, INC.

Lease Name. BARBER Well No. 1

Office Address. RUSSELL, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole). DRY HOLE

Date well completed. 9/18 19. 47

Application for plugging filed. 9/18 19. 47

Application for plugging approved. 9/18 19. 47

Plugging commenced. 9/18 19. 47

Plugging completed. 9/18 19. 47

Reason for abandonment of well or producing formation. DRY HOLE

If a producing well is abandoned, date of last production. 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well. C. D. STOUGH

Producing formation. Depth to top. Bottom. Total Depth of Well. 3740 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	186'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED WITH HEAVY MUD TO 186' - PLUG AND 15 SX CEMENT - FILLED WITH MUD TO 25' - PLUG AND 10 SX CEMENT.

9/25/47

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R DRILLING, INC.
Address. RUSSELL, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. L. ROBERTS

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

RUSSELL, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 23RD day of SEPTEMBER, 19 47

[Signature]

Notary Public.

My commission expires 6/17/50

21-6858-RS 2-47-6M

PLUGGING
FILE SEC 31 T 9 R 18W
BOOK PAGE 134 LINE 32

B & R DRILLING, INC.
BARBER #1

SEC. 31 TWP. 9 RGE. 18W
COUNTY: ROOKS

TOTAL DEPTH: 3740'
COMM: 9/5/47 COMP: 9/19/47

TOP TOPEKA - 3142'
" HEEBNER - 3355'
" DODGE - 3376'
" LANSING - 3398'
" CONGLOMERATE - 3632'
" ARBUCKLE - 3710'

CASING
9 Jts. 8 5/8" SET AT 186'

CEMENT
100 SX

FORMATION:	DEPTH:
SURFACE CLAY	30'
SAND	35
SHALE & SHELLS	120
SAND, SHALE & SHELLS	156
SHALE	186
SHALE, SHELLS & WHITE GYP	720
SAND	732
SHALE & SHELLS & SAND	990
SHALE & SHELLS	1130
SHALE & SAND	1265
SHALE & RED ROCK	1510
SHALE, RED ROCK, IRON STKS	1540
SHALE & RED ROCK	1615
ANHYDRITE	1649
SHALE, SHELLS & RED ROCK	1730
SHALE & SHELLS	1895
SHALE, SHELLS & SALT	2035
LIME & SHALE	2445
LIME	2470
SHALE & LIME	2475
LIME	2515
SHALE & LIME	3142
LIME	3285
LIME & SHALE	3360
LIME	3632
CONGLOMERATE, CHERTY	3710
ARBUCKLE LIME	3735
LIME	3740

STATE OF KANSAS)
) SS
RUSSELL COUNTY)

I HEREBY CERTIFY THAT THE ABOVE INFORMATION IS TRUE
AND CORRECT TO THE BEST OF MY KNOWLEDGE.

Clara Lumm

SUBSCRIBED AND SWORN TO BEFORE ME THIS 23RD DAY OF SEPTEMBER, 1947.

Clara Lumm
NOTARY PUBLIC

MY COMMISSION EXPIRES 6/17/50

9/24/47
Received

PLUGGING
FILE SEC 31 T 9 R 18W
BOOK PAGE 134 LINE 32