


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plat

Rooks \_\_\_\_\_ County. 31 Twp. 9 Rge. 18 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_

NW SE NW  
Lease Owner Edmiston Oil Co., Inc.  
Lease Name Mayhew Well No. 1  
Office Address 800 Vickers KSB&T Bldg, Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Dry Hole

Date Well completed June 15 19 77  
Application for plugging filed June 15 19 77  
Application for plugging approved June 15 19 77  
Plugging commenced June 15 19 77  
Plugging completed June 15 19 77  
Reason for abandonment of well or producing formation \_\_\_\_\_  
Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_  
19 \_\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3735'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Hole full of heavy mud to 660' pumped 70 sacks 50/50 Pozmix, 6% Gel thru drill pipe.  
Mud to 240' w/20 sacks 50/50 Pozmix, 6% Gel, thru drill pipe.  
Mud to 49' w/ $\frac{1}{2}$  sack hulls plug and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.  
Larry Curtis (employee of owner) or (owner/operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature)

Larry Curtis  
Box 823, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 1977

My commission expires April 11, 1978

Wanda M. Hague  
6/17/77  
Notary Public.  
Wichita, Kansas

15-163-20704-00-00

DRILLERS' WELL LOG

DATE COMMENCED: June 7, 1977  
DATE COMPLETED: June 15, 1977

Edmiston Oil Co., Inc.  
MAYHEW # 1  
NW SE NW  
Sec 31-T9-R18  
Rooks County, Kansas

ELEVATION: 2186 K.B.

0 - 817'	Clay and Shale
817 - 1095'	Shale, Sand Streaks
1095 - 1599'	Sand, Shale
1599 - 1640'	Anhydrite
1640 - 1671'	Shale
1671 - 2475'	Shale and Lime
2475 - 3070'	Lime and Shale
3070 - 3352'	Lime
3352 - 3356'	Shale
3356 - 3735'	Lime
3735'	RTD

FORMATION DATA

Anhydrite	1599
Heebner	3352
Toronto	3378
Lansing	3396
RTD	3735

SURFACE PIPE:  
Set used 8 5/8", 28# pipe  
at 248' w/160 sacks Common,  
2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS }  
COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 16th day of June, 1977.

Deborah M. Hague  
Notary Public

My Commission Expires: April 11, 1978

6/17/77  
JUN 17 1977