

STATE OF KANSAS
STATE CORPORATION
COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-163-⁰¹⁵⁶⁰⁻⁰⁰⁻⁰⁰95164

LEASE NAME Rempe "A"

WELL NUMBER #1

990' ^{100'} Ft. from S Section Line

~~2330'~~ ^{2310'} Ft. from E Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days

LEASE OPERATOR OXY USA Inc.

SEC 21 TWP 9 RGE 18W E or W

ADDRESS 110 S. Main # 800

COUNTY Rooks

PHONE# (316 265-5624) Operators License 5447

Date Well Completed 06/23/47

Character of Well oil

Plugging Commenced 03/27/96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 03/27/96

The plugging proposal was approved on 03/27/96 (Date)

by Dennis Hamel (KCC District Agent's name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Arbuckle Depth to Top 3570 Bottom 3575 T.D. 3575

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle		3570'	3575'	8 5/8"	1496'	
				5 1/2"	3570'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ Feet to ___ Feet each set.

See back for details.

RECEIVED
KANSAS CORPORATION COMMISSION
License No
7-3-96
CONSERVATION DIVISION
WICHITA, KS

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc.

Address 332 W Wichita, Russell, Kansas 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc

STATE OF Kansas COUNTY OF Sedgwick, ss.

Timothy J. Voss (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Timothy J. Voss
(Address) 110 S. Main Wichita Kansas 67202

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 19 96
Stephen E. Darwin
Notary Public

STEPHEN E. DARWIN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 3-9-99

My Commission Expires: 3/9/99

PULLED IN 1991 READY TO RUN

REMPE A 1

=====

3/17/96 JOB: Plug and Abandon; CMIC: JD HININGER
P&A - Perf. @ 1475' w/ 2 holes - cemented dn 8 5/8" w/ 150 sk 60/40
pozmix w/ 10% gel (Allied) plus 200# hulls - max press. - 100 psi -
shut in 100 psi - pumped dn 5 1/2" w/ 275 sk plus 300# hulls - max
press - 500 psi - shut in 400# psi - P&A @ 10:00 AM - 3/27/96 - State
witness Dennis Hamel -
L/E \$ 4950; CUM: L/E \$ 4950, TOT \$ 4950;

Geol. 63 500 5-47

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Reape
 Location 990' N and 330' E of S/4 Cor Sec. 21 T 9 R. 18W
 Elevation 2167 (2165G) County Rooks State Kansas
 Drlg. Comm. 6-4-47 Contractor R. W. Rine Drilling Co.
 Drlg. Comp. 6-23-47 Acid None
 T. D. 3575' Initial Prod. Echometer potential: 3000 oil, no wtr, 24 hrs., (7-3-47)
Ind. Cap. 5553 bbls.

CASING RECORD:

8-5/8" @ 1496 with 450 sx. cement.
 Perforated 8 shots 1082-85 and squeezed 375 sx. cem behind 8-5/8" casing.
 Perforated at 400' and squeezed 200 sx. cem. behind 8-5/8" casing; cement circulated.
 5-1/2" @ 3570' with 150 sx. cem.

Corr. Top Lansing	3321-1156
Corr. Top Arbuckle	3569
Penetration	6
Total Depth	3575

Fill-up

760' oil in 20 mins.
 1500' oil in 50 mins.
 1800' oil in 1 hour 15 mins.
 2400' oil in 6 1/2 hours.

Syfo

250' 1°
 500' 00
 750' 1°
 1000' 1°
 1250' 1°
 2000' 00°
 2500' 00°

FORMATION RECORD:

Shale, sand and shells	0-660
Shale and sand	1010
Sand, shale and shells	1270
Shale	170
Shale and shells	1460
Sand	1470
Shale and shells	1493
Anhydrite	1535
Shale and shells	2310
Lime	2385
Shale and shells	2620
Lime	2715
Shale and shells	2815
Shale	2945
Shale and lime	3070
Shale	3140
Lime and shale	3215
Lime	3519
Lime and shale	3577
3577 Rotary T.D. = 3574 SIM	
Lime	3575 T.D.

3321
 1156

RECEIVED
 KANSAS CORP COMM
 1946 MAR 11 A 9:41