

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

#6 15-163-03363-00-00

API NUMBER 05/06/47

LEASE NAME A. STAHL

WELL NUMBER 1

2970 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 21 TWP. 9S RGE. 18 (E) or (W)

COUNTY ROOKS

Date Well Completed 05/06/47

Plugging Commenced 4/28/87

Plugging Completed 4/29/87

LEASE OPERATOR CHEVRON U.S.A. INC.

ADDRESS P.O. BOX 12116, OKLAHOMA CITY, OK 73157

PHONE# (405) 949-7000 OPERATORS LICENSE NO. 4519

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? #6, HAYS, KS

Is ACO-1 filed? NO RECORD If not, is well log attached? YES

Producing Formation LANSING-KANSAS CITY Depth to Top 3367' Bottom 3429' T.D. 3598'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LANSING-KC	OIL	3367	3429	8-5/8	1504	-0-
				5-1/2	3579	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

SET CIBP @ 3460', DUMP 2 SX CMT ON TOP OF SAME. SET CIBP @ 3300'. TTH W/TBG TO 3300'. SPOT 10 SX 65-35 POZ MIX CMT, PULL TBG TO 3150', PMP 90 BRLS 9 0 PPG FW MUD, HOLE DID NOT FILL. POOH W/TBG. HOOK UP TO 5-1/2" X 8-5/8" ANNULUS, PMP 240 SX 65-35 POZ MIX CMT DOWN 8-5/8" X 5-1/2" ANNULUS, CIRC CMT TO SURFACE THRU 5-1/2" CSG, TOP OFF W/5 SX CMT. CUT OFF CSG, CAP & ID WELL.

Name of Plugging Contractor N/A License No.

Address

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

MICHAEL MCCARTHY (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael McCarthy

(Address) P.O. BOX 12116 OKLAHOMA CITY, OK. 73157

SUBSCRIBED AND SWORN TO before me this 29 day of MAY, 1987

RECEIVED STATE CORPORATION COMMISSION

Notary Public

My Commission Expires: SEPTEMBER 16, 1989

JUN - 1 1987 6-1-87

WELL LOG ON ADAM STAHL #1

Spudding Date: 5/6/47
 Date casing set: 5/18/47
 Date rotary completed: 5/18/47
 Date cable completed: 6-4-7

TOTAL DEPTH 3580'

Location:
 Section 21, Twp. 9S, Rge 18W,
 Rooks County, Kansas

FROM	TO	FORMATION	REMARKS
0	1275	Shale and shells	
1275	1395	Shale and red rock	
1395	2000	Shale and shells	Ran 73 jts. 8-5/8"
2000	2170	Shale and lime	Set at 1504' with 600 sacks
2170	2185	Lime	bulk cement.
2185	2960	Lime and shale	
2960	3025	Lime	
3025	3205	Lime and shale	
3025	3580	Lime	
3580	TOTAL DEPTH		

Deepened with Cable Tools 3598' TD
 Ran 111 jts. 5-1/2" casing.
 Cemented with 100 sacks bulk cement.

Subscribed and sworn to before me this
 30th day of May, 1947.

I certify the above and foregoing to be
 a true and exact copy of the original
 driller's log on the Adam Stahl #1

Chester J. Moon
 Notary Public

B E Rogers

My commission expires: 11/4/50