

15-163-09230-00-02

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION

12-31-97
TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.
CONSERVATION DIVISION
Wichita, Kansas

API NUMBER 15- NA
LEASE NAME Paradise Creek
WELL NUMBER 201
210 KCC ops
330' ft. from S Section Line
2310' ft. from E Section Line

LEASE OPERATOR OXY USA INC.
ADDRESS P.O. Box D, Plainville, KS 67663
PHONE # 785-434-7681 OPERATOR'S LICENSE NO. 5447
Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply)

Spot Location _____
SEC 21 TWP 9 S RGE 18 or (W)
COUNTY Rooks
Date Well Completed _____
Plugging Commenced 12-8-97
Plugging Completed 12-8-97

The plugging proposal was approved on 11-4-97 (date)
by David P. Williams - Hays, KS (KCC District Agent's Name)

Is ACO-1 filed? On File If not, is well log attached? _____

Producing Formation LKC & Arbuckle Depth to Top 3367' Bottom 3584' T.D. 3584'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Pulled out
		5'	1500'	8-5/8"	1500'	0'
		0'	3572'	5-1/2"	3572'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

*** See back for details ***

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. NA
Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA INC.

STATE OF Kansas COUNTY OF Rooks, ss.
J.D. Hininger (Employee of Operator) or (Operator) of above-described well, being first duly sworn


on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J.D. Hininger
(Address) P.O. Box D, Plainville, KS

SUBSCRIBED AND SWORN TO before me this 12th day of December, 1997

Sheryln Axelson Notary Public

My Commission Expires:
5-20-2000



OXY U.S.A., Inc.
Well Chronological Report

12/30/97

PARADISE CREEK UNIT 201
=====

12/17/97 JOB: Plug and Abandon; CMIC: George Younger
12/8/97 - Plug and Abandon - Pumped dn 5 1/2" csg. w/25 sks. 60/40
pozmix plus 10% gel and 200 lbs. hulls followed with 20 sks gel
followed with 150 sks same cement and 300 lbs. hulls - shut in w/100
psi. -
Pumped dn 8 5/8 with 175 sks. cement and 400 lbs. hulls - shut in 100
psi.
12/10/97 - Topped off 5 1/2" with 10 sks. cement - State witness
Dennis Hamel - P&A 11:30 AM 12/10/97
12/16/97 - Cut off csg. - cleaned up location. - complete
L/E \$ 1197; MAT \$ 3315; CUM: L/E \$ 1197, MAT \$ 3315;

FILED (10)
STATE COMMISSION

DEC 31 1997

CONSERVATION DIVISION
Wichita, Kansas