

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

RECEIVED
OCT 30 2001
10 - 30 - 01
KCC WICHITA

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-163-23,150 -00-00
LEASE NAME Widman
WELL NUMBER #6
990
4290
Ft. from S Section Line
Ft. from E Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR VESS OIL CORPORATION

SEC. 21 TWP. 9S RGE. 18W (E) or (W)

ADDRESS 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

COUNTY Rooks

PHONE # (316) 682-1537 OPERATOR'S LICENSE NO. 5030

Date Well Completed 5/14/91

Character of Well oil

Plugging Commenced 9/25/01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/25/01

The plugging proposal was approved on 09/20/2001 (date)
by Dennis Hamel (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3578' Bottom 3596' T.D. 3640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			Casing Record			
Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	204'	
				5-1/2"	3639'	
				Cemented at 1470 w/375 sx		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pressured braden head to 1000#. Tied onto casing and pumped 25 sx 60/40 Poz w/10% gel, and 200# hulls; 10 sx gel; 175 sx cement. Pressured to 1500#. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Joel Stull License No. _____

Address Box 307, Natoma, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

W.R. Horigan (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says that: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) W.R. Horigan
(Address) 8100 E. 22nd St. N., Bldg. 300
Wichita, KS 67226

SUBSCRIBED AND SWORN TO before me this 22nd day of October 2001

My Commission Expires:

MICHELLE D. HENNING
NOTARY PUBLIC
STATE OF KANSAS
My Appl. Exp. 7/18/05

Notary Public

Form CP-4
Revised 05-88

OR

ALLIED CEMENTING CO., INC.

09994

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <i>9-25-01</i>	SEC <i>21</i>	TWP. <i>9</i>	RANGE <i>18</i>	CALLED OUT	ON LOCATION <i>4:30 PM</i>	JOB START	JOB FINISH <i>5:31 PM</i>
LEASE <i>Widman</i>	WELL # <i>6</i>	LOCATION <i>P. dille 10 W 2 W N 10 N</i>			COUNTY <i>ROCK</i>	STATE <i>KS</i>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)			RECEIVED				

CONTRACTOR *✓* **OCT 30 2001**

TYPE OF JOB *Plug*

HOLE SIZE _____ T.D. *KCC WICHITA*

CASING SIZE *5-1/2* DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED

225 lb 69/40-10

400 # Hells 10 lb Gel

used 200 lb

COMMON	<i>120</i>	@	<i>6.65</i>	<i>798.00</i>
POZMIX	<i>80</i>	@	<i>3.55</i>	<i>284.00</i>
GEL	<i>30</i>	@	<i>10</i>	<i>300.00</i>
CHLORIDE		@		
<i>Hells 4</i>		@	<i>18.00</i>	<i>72.00</i>
		@		
		@		
		@		
		@		
HANDLING	<i>259</i>	@	<i>110</i>	<i>284.90</i>
MILEAGE	<i>1.04/m/ck</i>			<i>414.40</i>
TOTAL				<i>2153.30</i>

EQUIPMENT

PUMP TRUCK CEMENTER *Bill*

345 HELPER *Mark*

BULK TRUCK

254 DRIVER *Shane*

BULK TRUCK

_____ DRIVER _____

REMARKS:

pump in Ann. press to 500#

no cement

pump down 5 1/2' 25 lb cement

w/ 260 # Hells followed 10 lb gel

follow w/ 125 lb cement w/ 30 lb Hells

press to 1500 # shut in

SERVICE

DEPTH OF JOB *2nd well* *225.00*

PUMP TRUCK CHARGE _____

EXTRA FOOTAGE _____ @ _____

MILEAGE *4 @* @ *3.00* *120.00*

PLUG _____ @ _____

_____ @ _____

_____ @ _____

2498.3

249.83

2748.47

TOTAL *345.00*

CHARGE TO: *Urss*

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____