

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

SEP 05 2003
KCC WICHITA

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-163-23,134-00-00

LEASE NAME Widman

WELL NUMBER #5

990 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 21 TWP. 9 RGE. 18 (E) of (W)

COUNTY Rooks

Date Well Completed 2/7/91

Plugging Commenced 8/8/03

Plugging Completed 8/8/03

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

PHONE # (316) 682-1537 OPERATOR'S LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/10/2002 (date)
by David Williams w/ KCC (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Arbuckle Depth to Top 3578' Bottom 3580' T.D. 3680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	221'	none
				5-1/2"	3674'	none
				perfd and squeezed	1450'	w/300 sx - circ

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Ran tbg to 2030' and stacked out. KCC okayed to plug here. Spotted 5 sx gel, 25 sx 60/40 poz w/10% gel w/200# hulls.

Circulate to surface. Pulled tbg to 1450' Circ hole w/80 sx same cement w/100# hulls. TOH w/tbg. Pumped down 5-1/2" csg.

w/20 sx same cement - MP -800#. SIP - 700#. Connected to 8-5/8 and 5-1/2" annulus and pumped 5 sx - 800#. Approved by Dennis Hamel - KCC

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cement Company License No. 30437

Address P.O. Box 31, Russell, KS 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

W.R. Horigan (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says that: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

WR Horigan


(Address)

8100 E. 22nd St., North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED AND SWORN TO before me this 3rd day of September 2003

Michelle D. Henning
Notary Public

My Commission Expires:



Form CP-4
Revised 05-88

ALLIED CEMENTING CO., INC. 14235

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Russell

DATE <u>8/8/03</u>	SEC.	TWP.	RANGE	CALLED OUT <u>7:00 AM</u>	ON LOCATION <u>8:45 AM</u>	JOB START	JOB FINISH <u>11:30 AM</u>
LEASE <u>widman</u>	WELL # <u>5</u>	LOCATION <u>Pelle 120 12 4 W</u>			COUNTY <u>Rocky</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)				RECEIVED			

CONTRACTOR ~~Smoky Hill~~ OWNER _____

TYPE OF JOB plug

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE 2 3/8 DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

SEP 05 2003

KCC WICHITA

CEMENT AMOUNT ORDERED _____

175 db 60/40-10 used 130 db

300 #Hulls 5 db Gel

COMMON <u>78</u>	@ <u>7.15</u>	<u>557.70</u>
POZMIX <u>52</u>	@ <u>3.80</u>	<u>192.60</u>
GEL <u>16</u>	@ <u>10.00</u>	<u>160.00</u>
CHLORIDE _____	@ _____	_____
<u>Hulls 3</u>	@ <u>18.00</u>	<u>54.00</u>
_____	@ _____	_____
_____	@ _____	_____
_____	@ _____	_____
_____	@ _____	_____
HANDLING <u>175</u>	@ <u>1.15</u>	<u>201.25</u>
MILEAGE <u>.05/sk/mi</u>		<u>45.00</u>
TOTAL		<u>1620.55</u>

EQUIPMENT

PUMP TRUCK CEMENTER Bill

177 HELPER Shave

BULK TRUCK

362 DRIVER Rufus

BULK TRUCK

_____ DRIVER _____

REMARKS:

Tekinsc 2030 pump 5 db Gel
Follow w/ 25 db Cement w/ 200 #Hulls
pull to 1450' pump 8 db Cement w/ 100 #Hulls
Circ. to surface, pull Tekinsc.
pump down 5' w/ 200# press to 800 #
Hold 700 #
BACKSIDE 5 db Cement. press to 800 #
SHUT-IN

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 475.00

EXTRA FOOTAGE @ _____

MILEAGE 52 @ 3.50 182.00

PLUG @ _____

_____ @ _____

_____ @ _____

TOTAL 675.00

CHARGE TO: Wess

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____