

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Daystar Petroleum, Inc.
Address: PO Box 360, Valley Center, KS 67147
Phone: (316) 755-3523 Operator License #: 30931
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8/17/06 (Date)
by: Darrel Dipman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Lansing/ KC Depth to Top: 4000 Bottom: 4240 T.D. 4400

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-153-20,703-00-00
Lease Name: Timm
Well Number: 1
Spot Location (QQQQ): C - SW - NW - NE
990 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 24 Twp. 15 S. R. 33 East West
County: Rawlins
Date Well Completed: 2/11/88
Plugging Commenced: 8/17/06
Plugging Completed: 8/17/06

KCC PLOT
4/10/07
Per
OP-23

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing/ KC	Oil/ water	Surface	302	8 5/8"	302	-0-
		Surface	4394	4 1/2"	4394	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pump 215 sx 60/40 poz w/ 500# hulls from surface @ 200 psi
Top off 4 1/2" csg w/ 10 sx 60/ 40 poz + 50# hulls
Pump 20 sx cement down 8 5/8"; pressure to 20 psi

Name of Plugging Contractor: Plains, LLC License #: 33645
Address: PO Box 346, Ness City, Kansas

Name of Party Responsible for Plugging Fees: Daystar Petroleum, Inc.
State of Kansas County, Sedgwick, ss.

Charles Schmidt (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Charles Schmidt

Notary Public - State of Kansas
MARSHA BREITENSTEIN
My Appointment Expires 9-15-07

(Address) PO Box 360, Valley Center, KS 67147
Subscribed and SWORN TO before me this 2nd day of April, 20 07

Marsha Breitenstein My Commission Expires: Sept 15, 2007
Notary Public

RECEIVED
KANSAS CORPORATION COMMISSION
APR 03 2007
CONSERVATION DIVISION
WICHITA, KS

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT

ALLIED CEMENTING CO., INC.

24999

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

OAKLEY

DATE <u>8-17-06</u>	SEC. <u>24</u>	TWP. <u>15</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>9:00 AM</u>	JOB START <u>9:50 AM</u>	JOB FINISH <u>10:45 AM</u>
LEASE <u>JEMM</u>	WELL # <u>1</u>	LOCATION <u>Ludell 7N-1/2W-5 IN</u>			COUNTY <u>RAWLINS</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR NONE

TYPE OF JOB OLD HOLE

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2" DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER SAME

CEMENT

AMOUNT ORDERED 500# HULLS

260 SKS 60/40 POZ 100 GEL

USED 235 SKS 60/40 POZ 100 GEL 500# HULLS

COMMON	<u>141 SKS</u>	@	<u>12²⁰/₁₀₀</u>	<u>1720²⁰/₁₀₀</u>
POZMIX	<u>94 SKS</u>	@	<u>6¹⁰/₁₀₀</u>	<u>573¹⁰/₁₀₀</u>
GEL	<u>20 SKS</u>	@	<u>16⁶⁵/₁₀₀</u>	<u>333⁶⁵/₁₀₀</u>
CHLORIDE		@		
ASC		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>287 SKS</u>	@	<u>1⁹⁰/₁₀₀</u>	<u>545⁹⁰/₁₀₀</u>
MILEAGE	<u>94 PER SK</u>			<u>1704⁷⁰/₁₀₀</u>
TOTAL				<u>5004¹⁰/₁₀₀</u>

EQUIPMENT

PUMP TRUCK # 191 CEMENTER TERRY
HELPER WAYNE

BULK TRUCK # 399 DRIVER LOWRICE

BULK TRUCK # _____ DRIVER _____

REMARKS:

HOOK ON TO 4 1/2" CASING. MIX
215 SKS CEMENT WITH 500# HULLS
MAX PSE 200. NO SHUT IN PRESSURE

MIX 20 SKS CEMENT down BACKSIDE
MAX PRESSURE 200 PSE. BLEW HEAD
NO SHUT IN PRESSURE

THANK YOU

CHARGE TO: DAYSTAR petroleum, INC.

STREET _____

CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 955⁰⁰/₁₀₀

EXTRA FOOTAGE _____ @ _____

MILEAGE 66 mi @ 6⁰⁰/₁₀₀ 396⁰⁰/₁₀₀

MANIFOLD _____ @ _____

_____ @ _____

_____ @ _____

TOTAL 1351⁰⁰/₁₀₀

PLUG & FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME RECEIVED
KANSAS CORPORATION COMMISSION

APR 03 2007

CONSERVATION DIVISION
WICHITA, KS