

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: W. D. Short Oil Co., LLC
Address: P. O. Box 729-102 S. River Rd., Oxford, Ks. 67119
Phone: (620) 455 - 3576 Operator License #: 33608
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: May 19, 2006 (Date)
by: David Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Lime Depth to Top: 3155 Bottom: 3171 T.D. 3171

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 035-02193 - 00 - 00
Lease Name: Jesse Rahn
Well Number: 1
Spot Location (QQQQ): C - NE - NE - NW
330 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 11 Twp. 34 S. R. 5 East West
County: Cowley
Date Well Completed: 08-12-1963
Plugging Commenced: 02-07-2007
Plugging Completed: 03-15-2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi Lime	Oil	3155	3171	8-5/8"	224	0
				4-1/2"	3155	1330'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Set Bottom Pug, Sanded Back to 3105' and Dumped 4 sx of Cement on top of sand w/ Dump Bailer, Worked Pipe and Shot off @ 1330',
Laid out pipe, Filled hole w/ Water, Ran 1" pipe to 275' and Pumped Cement to Surface, 98 sx w/ 4% Gel, Topped
Off Hole w/ cement, Cleaned up and Restored Location.

Name of Plugging Contractor: Braden Petroleum & Well Plugging License #: 32475
Address: P.O. Box 282, Burden, Ks. 67019
Name of Party Responsible for Plugging Fees: W. D. Short Oil Co., LLC
State of Kansas County, Cowley, ss.
William D. (Don) Short, Jr.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P.O. Box 729, 102 S. River Rd. Oxford, Ks. 67119

SUBSCRIBED and SWORN TO before me this 3rd day of April, 2007
[Signature] My Commission Expires: 3-30-09
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
APR 05 2007
CONSERVATION DIVISION
WICHITA, KS

P167

B.P.C. WELL PLUGGING

P.O. BOX 282
BURDEN, KS 67019

JAMES R. BRADEN
HOME # 620-438-2856 MOBILE # 620-222-1252

DATE	INVOICE #
3/27/2007	07/555

BILL TO
SHORT COMPANIES P.O. BOX 729 OXFORD,KS.67119

JOB LOCATION
JESSE RAHN #1

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
2/7/2007		MOVED IN ON LOCATION. RIGGED UP TO PLUG BOTTOM. SANDED BACK TO 3105', DUMPED 4 SX. CEMENT ON TOP OF SAND WITH DUMP BAILER. DUG CELLAR, SET JACKS. PULLED SLIPS, WORKED PIPE.	
2/8/2007		WORKED PIPE, SHOT OFF @ 1330'. LAYED OUT 4 1/2" PIPE. LOADED JACKS, RIGGED DOWN.	
	RIG UP CHARGE		1,200.00T
	PIPE PULLING CHARGE	1330' OF 4 1/2" PIPE PULLED @ \$0.65 PER FT.	864.50T
	SHOOTING CHARGE	1 SHOT @ \$350.00 PER SHOT	350.00T

RECEIVED
KANSAS CORPORATION COMMISSION
APR 05 2007
CONSERVATION DIVISION
WICHITA, KS

Thank you for your business.	SUBTOTAL	\$2,414.50
	SALES TAX (5.8%)	\$140.04
	BALANCE DUE	\$2,554.54

B.P.C. WELL PLUGGING

P.O. BOX 282
BURDEN, KS 67019

JAMES R. BRADEN

HOME # 620-438-2856 MOBILE # 620-222-1252

DATE

INVOICE #

3/27/2007

07/563

BILL TO

SHORT COMPANIES
P.O. BOX 729
OXFORD, KS. 67119

JOB LOCATION

JESSE RAHN #1

TERMS 30 DAYS

Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
3/15/2007		MOVED IN ON LOCATION. RIGGED UP TO PUMP CEMENT. LOADED 40 BBL. WATER. RUN 1" DOWN INSIDE 85/8" SURFACE PIPE TO 275'. PUMPED 98 SX. CEMENT DOWN 1" FILLED TO THE SURFACE, PULLED 1" OUT. TOPPED OFF WITH CEMENT, WASHED UP. LOADED UP.	
	CEMENT	98 SACKS- 4% GEL @ \$7.35 PER SACK	720.30T
	PUMP CHARGE	3 HRS @ \$75.00 PER HR.	275.00T
	BULK TANK	\$100.00 PER JOB	100.00T
	WATER TRUCK	3 HRS. @ \$50.00 PER HR.	150.00T

RECEIVED
KANSAS CORPORATION COMMISSION

APR 05 2007

CONSERVATION DIVISION
WICHITA, KS

Thank you for your business.

SUBTOTAL

\$1,245.50

SALES TAX (5.8%)

\$72.23

BALANCE DUE

\$1,317.53