

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Globe Operating, Inc.
Address: P.O. Box 12 Great Bend, Ks. 67530
Phone: (620) 792-7607 Operator License #: 6170
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: B.J. Hope (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-155-21,236-00-00
Lease Name: Harris
Well Number: 1-22
Spot Location (OQQQ): 95'W of C. NE NW. NW
330 Feet from North / South Section Line
895 Feet from East / West Section Line
Sec. 22 Twp. 25 S. R. 9 East West
County: Reno
Date Well Completed: _____
Plugging Commenced: 3-13-07
Plugging Completed: 3-15-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	208'	None
				5-1/2"	3995'	2600'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3780' and 5 sxs. cement, Cut casing loose @2600', pulled up to 1323', pumped 35 sxs. cement, pulled up to 750', pumped 35 sxs. cement, pulled up to 260', pumped 80 sxs. cement and circulated to surface, 60/40 pos, 4% gel.

Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Globe Operating, Inc.
State of Kansas County: Rice ss.

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 21 2007
CONSERVATION DIVISION
WICHITA, KS

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 20th day of March, 2007

Irene Herzberg My Commission Expires: _____
Notary Public

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT