

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: BEREXCO, INC.

Address: PO BOX 723 HAYS, KS 67601

Phone: (785) 628-6101 Operator License #: 5363

Type of Well: OIL Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2-27-07 (Date)

by: JAY PFEIFER (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Table with 4 columns: Formation, Depth to Top, Bottom, T.D. Rows include L-KC with depths 3759, 63, 3980 and L-KC with depths 3855, 60, 3980.

API Number: 15-065-20032-00-00

Lease Name: KNOLL North Drilling 3/24/07

Well Number: D-4 1 PKF Pen T-1

Spot Location (QQQQ): W1/2 - NW - NE PERFBOM

660 Feet from North / South Section Line

1980 Feet from East / West Section Line

Sec. 32 Twp. 8 S. R. 25 East West

County: GRAHAM

Date Well Completed: 4-18-67

Plugging Commenced: 2-27-07

Plugging Completed: 2-28-07

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows show L-KC formations with oil/water content and casing records.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

MOVE IN WORKSTRING AND RIG UP PERF-TECH, PERF AT 2160' 2 HOLES PER KCC. TIH W/ 2-3/8 PLUGGING STRING TAG UP ON FISH AT 3649 PICK UP TO 3635' MIX 100 SKS W/ 200# HULLS PULL TBG TO 1500' AND MIX 75 SKS 6-1/4- 10% GEL W/ 200# HULLS. TOH AND RIG DOWN. MOVE RIG AND DUG OUT TO 8-5/8 TOP 4-1/2 CSG OFF W/ 25 SKS 60/40 10% TIC ONTON 8-5/8 PUMP 50 SKS 60/40 10% GEL. SHUT IN AT 400 PSI.

Name of Plugging Contractor: PROFESSIONAL PULLING SERVICE License #: 32810

Address: PO BOX 486 HAYS, KS 67601

Name of Party Responsible for Plugging Fees: MARK LEIKER

State of KS County, ELLIS, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Leiker

(Address) PO BOX 723 HAYS, KS 67601



Subscribed and SWORN TO before me this 6 day of MARCH, 20 07

Shanna Miller Notary Public My Commission Expires: 9-19-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED MAR 14 2007 KCC WICHITA