

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: R.P. Nixon Operations, Inc.

Address: 207 West 12th Street Hays, KS 67601

Phone: (785) 628-3834 Operator License #: 5252

Type of Well: SWD Docket #: D06484  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: KCC Pkt 3/29/07 Per (Date)

by: \_\_\_\_\_ (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☒ Yes ☐ No

Producing Formation(s): List All (if needed attach another sheet)

Cedar Hills disposal Depth to Top: 1460 Bottom: 1538 T.D. \_\_\_\_\_  
" " Depth to Top: 1402 Bottom: 1452 T.D. \_\_\_\_\_  
" " Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - drilled 4-16-58

Lease Name: Wiltout

Well Number: #6

Spot Location (QQQQ): C - NE - NE - NE  
330 Feet from ☒ North / ☐ South Section Line

330 Feet from ☒ East / ☐ West Section Line

Sec. 27 Twp. 5 S. R. 21 ☐ East ☒ West

County: Norton

Date Well Completed: 5-16-58

Plugging Commenced: 3-20-07

Plugging Completed: 3-20-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	228'	none
				5 1/2"	3642'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Allied Cementing tied on to 8 5/8" annulus and pressured to 500#. Tied on to 5 1/2" casing and pumped 200 sacks of 60/40 cement, 10% gel with 600# of hulls in the first 50 sacks. Well took cement on vacuum. 1 1/2 hours after pumping cement down casing, cement was at approximately 300' (6 seconds down). KCC could not be present for plugging job. Came back the next day (2-21-07) and filled casing with 2 yards of Redimix, as recommended by Herb Deines (KCC District 4).

Name of Plugging Contractor: R.P. Nixon Oper., Inc. License #: 5252


Address: 207 West 12th Street Hays, KS 67601

Name of Party Responsible for Plugging Fees: R.P. Nixon Operations, Inc.

State of Kansas County, Ellis, ss.

Dan A. Nixon, president of R.P. Nixon Oper., Inc.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]  
(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 22nd day of March

, 20 07

Gloria B. Lang  
Notary Public

My Commission Expires: 3-12-2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
MAR 23 2007  
KCC WICHITA

ALLIED CEMENTING CO., INC.

33111

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: K

DATE <u>3-30-67</u>	SEC. <u>27</u>	TWP. <u>S</u>	RANGE <u>21W</u>	CALLED OUT	ON LOCATION	JOB START <u>10:30AM</u>	JOB FINISH <u>11:00AM</u>
LEASE <u>10000</u>	WELL # <u>X-6</u>	LOCATION <u>LOAN 10-5-5-1-1</u>				COUNTY <u>LABETTE</u>	STATE <u>KS</u>
OLD OR NEW (Circle one)							

CONTRACTOR		OWNER	
TYPE OF JOB <u>PTA</u>			
HOLE SIZE	T.D.	CEMENT	
CASING SIZE <u>2 1/2</u>	DEPTH <u>3-12</u>	AMOUNT ORDERED <u>20000</u>	
TUBING SIZE	DEPTH		
DRILL PIPE	DEPTH		
TOOL	DEPTH		
PRES. MAX	MINIMUM		
MEAS. LINE	SHOE JOINT		
CEMENT LEFT IN CSG.			
PERFS.			
DISPLACEMENT			

EQUIPMENT			
PUMP TRUCK	CEMENTER <u>John</u>		
#	HELPER <u>John</u>		
BULK TRUCK			
#	DRIVER <u>Richard</u>		
BULK TRUCK			
#	DRIVER		

REMARKS:	TOTAL
<u>DATA 1500</u>	
<u>PTA 8-2 to 500</u>	
<u>PTA 500 to 500</u>	
<u>No pressure</u>	
<u>on val</u>	
<u>THANKS</u>	

CHARGE TO: <u>RP actual</u>	TOTAL
STREET	
CITY	STATE
ZIP	

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE <u>Duane Achterberg</u>	PRINTED NAME <u>Duane Achterberg</u>
-----------------------------------	--------------------------------------

SERVICE	
DEPTH OF JOB	
PUMP TRUCK CHARGE	
EXTRA FOOTAGE	@
MILEAGE	@
MANIFOLD	@
	@
	@

PLUG & FLOAT EQUIPMENT	
	@
	@
	@
	@
	@

TOTAL
TAX
TOTAL CHARGE
DISCOUNT
IF PAID IN 30 DAYS

JOCELYN-VARN OIL COMPANY  
310 KPH BUILDING  
WICHITA 2, KANSAS

RE: Wilttrout #6  
NE NE NE  
Sec. 27-T55-R21W  
Norton County, Kansas

elev. 2223

Prod. Day

Comm. 4-16-58  
Comp. 5-16-58  
Conts. Tusco Oil Co.

Casing: 8" 223'  
FORMATION 5" 3642'

	TOP	BOTTOM
Soil & Clay	0	40
Sand & Gravel	40	120
Shale	120	223
Shale & Shells	223	1020
Sand	1020	1260
Shale & Shells	1260	1366
Sand	1366	1550
Shale & Shells	1550	1813
Anhydrite	1813	1848
Shale & Shells	1848	2190
Shale & Shells w/lime strks	2190	2400
Lime & Shale	2400	2920
Lime	2920	3202
Lime & Shale	3202	3255
Lime	3255	3497
Lime & Chert	3497	3530
Lime	3530	3564
Lime & Shale	3564	3644 R.T.D.
		3661

Laps: Scout

Heeb 3363

Jol 3390

Lans 3406

arb 3641

Reag 3660

The Above is True and Correct

E. H. Sloyer  
Partner

RECEIVED  
MAR 23 2007  
KCC WICHITA