

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Black Star 231 Corp  
Address: 2300 Main St. Suite 900, Kansas City, Mo, 64108  
Phone: (816) 560-7300 Operator License #: 31772  
Type of Well: D&A Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 3-5-07 (Date)  
by: Mike Hefron (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Absent- D&A Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-073-24053-0000 *KCC P197*  
Lease Name: Schoenhals *3/29/07*  
Well Number: 1-07 *per CP 2/3*  
Spot Location (QQQQ): apSE-NE-NE-  
3597 Feet from  North /  South Section Line  
987 Feet from  East /  West Section Line  
Sec. 35 Twp. 27 S. R. 29E  East  West  
County: Greenwood  
Date Well Completed: 3-6-07  
Plugging Commenced: 3-6-07 11:00 am  
Plugging Completed: 3-6-07


Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Cattleman	oil show	2137	2140	8 5/8"	200'	-0-
Mississippian	oil show	2350	2360			
Arbuckle	oil show	2702	2730			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.  
Hole was circulated clean with heavy drill mud. Cement plugs were spotted through drill pipe. 1st 50' plug @ 2667', 2nd 50' plug @ 2322', 3rd 50' plug @ 790', One continuous plug from 260' to land surface.

Name of Plugging Contractor: Consolidated Oil Well Service License #: 04996 31440  
Address: P.O. Box 884, Chanute, Ks., 66720  
Name of Party Responsible for Plugging Fees: Black Star 231 Corp, Jim Pryor  
State of Missouri County, Platte, ss.  
Jim Pryor

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]  
(Address) 2300 Main St, suite 900, Kansas City, Mo, 64108

SUBSCRIBED and SWORN TO before me this 19 day of MARCH, 2007  
Leonard L. Hopkins My Commission Expires: 12-6-2008  
Notary Public

RECEIVED  
KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 **MAR 21 2007**

CONSERVATION DIVISION  
WICHITA, KS *per*