

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Phoenix PetroCorp, Inc.  
Address: 15700 Custer Trail, Frisco, TX  
Phone: (972) 529-2544 Operator License #: 32659  
Type of Well: Oil EOR KCC Pkt per CP213 Docket #: E 18039  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 3/3/2006 (Date)  
by: Mr. Steve Durrant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Morrow Depth to Top: 5001' Bottom: 5011' T.D. 5175'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 1292006600 01  
Lease Name: Berryman Richfield Unit  
Well Number: 12-1 W KCC Pkt per CP213 10/12/06  
Spot Location (QQQQ): W/2 - NE - NE -  
660 Feet from  North /  South Section Line  
810 Feet from  East /  West Section Line  
Sec. 3 Twp. 33S S. R. 41  East  West  
County: Morton  
Date Well Completed: March 1971 original  
Plugging Commenced: 4/10/06  
Plugging Completed: 4/10/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Morrow		5001	5011	4-1/2"	5175	-0-
SURF				8.625	1510'	
CIBP					1710'	
PKR					4656'	


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP @ 1710' WITH 2 SX CEMENT, PULL UP TO 1525' PERF CASING. OPEN WELL UP, BREAK CIRCULATION WITH 40 BBLs OF LEASE WATER, GETTING RETURNS TO SURFACE, PUMP 425 SX OF 60/40 POZ CEMENT, LOST CIRCULATION PUMP 20 SX OF 60/40 POZ DOWN ANNULUS. 8 HOURS LATER, PUMP 25 SX 60/40 POZ DOWN CSG. CSG LOADED UP, PUMP 90 SX 60/40 POZ CEMENT DOWN SURFACE CASING, SURFACE CASING LOADED UP, CEMENT @ SURFACE.

Name of Plugging Contractor: Phoenix PetroCorp, Inc. Key Energy Services License #: 32659 33223  
Address: 15700 Custer Trail, Frisco, Tx 75035 KCC Pkt 4/13/07 Per open-  
Name of Party Responsible for Plugging Fees: Phoenix PetroCorp, Inc. 15700 Custer Trail, Frisco, Tx 75035 James Williams  
State of Texas County, Collin, ss.  
James H. Williams

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is filed, and the same are true and correct, so help me God.

(Signature) James H Williams **RECEIVED APR 25 2006**  
(Address) 15700 Custer Trail, Frisco, Tx 75035 **KCC WICHITA**



SCRIBED and SWORN TO before me this 24th day of April, 2006  
Cindy J. Tarbox My Commission Expires: 71 March 30, 2008  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED 4-25-06