

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-00353-00-00
Spot: SESWNW Sec/Twnshp/Rge: 17-19S-1W
2956 feet from S Section Line, 4395 feet from E Section Line
Lease Name: KOEHN B Well #: 1
County: MCPHERSON Total Vertical Depth: 3020 feet

Operator License No.: 3822
Op Name: KOEHN, ELDON R.
Address: 2241 MOCCASIN ROAD
GALVA, KS 67443

\$ 98.15

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/24/2007 9:30 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: AARON KOEHN Company: KIZZAR WELL SERVICING, INC. Phone: (620) 654-8656

Proposed Plugging Method: AS PER KCC REG.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/24/2007 10:20 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

SET CIBP @ 2800' AND CAP WITH 3 SKS CEMENT, PERFORATE CASING @450' AND SET BRIDGE @500'. RUN TUBING TO 470' AND CIRCULATED CEMENT TO SURFACE. I WAS NOT PRESENT TO SEE THIS, BUT DID VERIFY WITH AARON KOEHN THAT THE CEMENT DID CIRCULATE INSIDE AND OUTSIDE OF CASING. RECHECKED ON 1/25/07 TO SEE CEMENT AT SURFACE.

INVOICED
DATE 4-2-07
INV. NO. 2007061533

Remarks: UNITED CEMENTING CO. TICKET # 7540, USED 60/40 POZMIX W/4% GEL; LOG TECH TICKET#4789 & 4819.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

RECEIVED
(TECHNICAL)
KANSAS CORPORATION COMMISSION

MAR 28 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

a

Post