

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-15693-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 6-16S-12W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease Name: DEPIESSE Well #: 8  
County: BARTON Total Vertical Depth: 3301 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3296	0	w/unknown sxs cmt
SURF	7	309	0	w/unknown sxs cmt

\$107.28

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/22/2007 10:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: BOB GRANT Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 800# hulls.  
Plug through tubing and squeeze casing.  
Perf at 1475' - 815' - 200'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/22/2007 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing in 5 1/2" casing to 2642' - pumped 100 sxs cement with 300# hulls - good circulation of fluid.  
Pulled tubing to 1318' - pumped 100 sxs cement with 250# hulls - good circulation of fluid.  
Pulled tubing to 648' - pumped 50 sxs cement with 125# hulls - good circulation of cement.  
Tied onto casing - squeezed with 65 sxs cement with 125# hulls.  
Max. P.S.I. 250#. S.I.P. 100#.  
Tied on to 7" surface - squeezed with 50 sxs cement.  
Max. P.S.I. 400#. S.I.P. 100#.  
Pumped 35 sxs in void in annulus.

Perfs:


**INVOICED**  
DATE 4-2-07  
INV. NO. 2007061529

Remarks: LEASE RE-NAMED NW BEAVER UNIT #8-8. ALLIED CEMENTING COMPANY-TICKET #21177.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

RECEIVED

MAR 27 2007

KCC WICHITA

Form CP-2/3

MAR 22 2007



FRANCO CENTRAL

#8

DEPIESSE

6-16-12W  
NW NE SE

Contr.

BARTON

County

E 1859

Comm.

Comp.

3-16-51

IP

75 BOPD


Tops	Depth	Datum
ANH	795	
TOP	2658	-799
DODGE	2966	-1107
BR LM	3025	-1166
LANS	3042	-1183
PENN SD	3293	-1434
ARB	3297	-1438
T.O.	3301	-1442

Casing

13" 410'  
 10" 797  
 8" 2435'  
 5" 3297'

DP & DD 3301: 1450' OIL/  
 7 HRS: PLUG 3210:  
 PERF 24 S, 3178-84: SSO  
 ACID 3000: SWB 1/4 BO &  
 16 1/2 BWP/24 HRS: SQZ:  
 PERF 3178-84:  
 PERF 24 S, 3041-47  
 GOOD SHOW OF OIL:  
 ACID 1000: EST 75 BOPD

BEAVER NW POOL



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS