

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-00176-00-00

Spot: E NWNWS E Sec/Twnshp/Rge: 10-31S-40W

2492-2640 Feet from N Section Line, 2497-2640 Feet from W Section Line *Per KC*

Lease Name: SMITH GAS UNIT A

Well #: 1

4-3-07

County: MORTON

Total Vertical Depth: 2516 feet

Operator License No.: 5952

Op Name: BP AMERICA PRODUCTION COMPANY

Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2140		WITH 2 SX CMT
PROD	5.5	2516	0	WITH 350 SX CMT
SURF	8.625	639		WITH 325 SX CMT

\$ 81.77

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 03/13/2007 10:00 AM

Plug Co. License No.: 33338

Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: JOE EUDEY

Company: BP AMERICA

Phone: (620) 356-6955

Proposed Plugging Method: PROCEDURES APPROVED BY STEVE DURANT-KCC. SET CIBP AT 2250. FILL CASING WITH WATER AND RUN CBL TO DETERMINE TOC. PERFORATE CIRCULATING HOLES. CIRCULATE CEMENT DOWN 5.5" CASING, THROUGH CIRCULATING HOLES, AND OUT ANNULUS BETWEEN THE 8.625" & 5.5" CASING. LEAVE THE 5.5" CASING AND THE ANNULUS FULL OF CEMENT FROM GROUND LEVEL TO CIRCULATING HOLES. CUT OFF AND CAP CASINGS 5' BELOW GROUND LEVEL. RESTORE LOCATION.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/13/2007 12:00 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

RAN BOND LOG. TOC @ 820'. PERFORATE AT 640'. PUMP 200 SX CMT. FILLED 5 1/2" & 5 1/2" X 8 5/8" ANNULUS FROM 640' TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2302	2488		

INVOICED
DATE 4-3-07
INV. NO. 2007061540

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01



Signed

Jim Holland
PART III
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 29 2007
CONSERVATION DIVISION
WICHITA, KS