

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,102-00-00

LEASE NAME Allphin

WELL NUMBER #1.

SPOT LOCATION NW SE NE

SEC. 32 TWP. 9S RGE. 19W(E) or (W)

COUNTY Rooks

Date Well Completed 08-23-83

Plugging Commenced 11-4-83

Plugging Completed 11-17-83

LEASE OPERATOR Frontier Oil Company

ADDRESS 125 N Market, Ste 1720, Wichita, Ks. 67202

PHONE # (316) 263-1201 OPERATORS LICENSE NO. 5140.

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes.

Which KCC/KDHE Joint Office did you notify? Hays, Ks. Carl Goodrow, witness 11-4-83; Marion Schmidt 11-17-83

Is ACO-1 filed? Yes. If not, is well log attached? _____

Producing formation N/A Depth to top _____ bottom _____ T.D. 3796'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface Pipe	200 sx	0'	329	8-5/8"	7-16-83	-0-
Casing	175 sx	0'	3758	5-1/2"	7-24-83	-0-
DV Tool @ 1650'	450 sx					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set. 5 sx cmt @ 1000# SI Annulus; 25 sx 50/50 Poz, 6% Gel, 3% CC in 5 1/2 to 3796'-3400'; 13 sx gel 3400-2100/25 sx 50/50 Poz, 6% Gel, 3% CC 2100-1750; 6 sx Gel 1750-1150; 70 sx cmt on top @ 700#. Cmt. dropped apx 250' from surf. Per Marion Schmidt filled top of csg w/apx 2 yards Allied Redi-mix to top of csg. J/C 11-17-83

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. N/A
Address P O Box 31, Russell, Ks. 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.


Jean Angle (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, **RECEIVED** and log of the above-described well **STATE CORPORATION COMMISSION** are true and correct, so help me God.

FEB 01 1984

2-1-84

CONSERVATION DIVISION

SUBSCRIBED AND SWORN to before me this 31 day of January, 1984



My Commission expires: _____

June 24, 1984

Notary Public