

15-16301706-00-00
 STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

RECEIVED Form CP-4
 STATE CORPORATION COMMISSION
 SEP 27 1982
 9-27-82
 CONSERVATION DIVISION
 Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rooks SEC. 32 TWP. 9S RGE. 19W E/W
 Location as in quarters or footage from lines:
C- N/2 NE SW

Locate Well
 correctly on above
 Section Platt.

Lease Owner Tomlinson Oil Co
 Lease Name Lynd Well No. 6
 Office Address 200 W Douglas, Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): oil
 Date Well Completed August 1961
 Application for plugging filed 8-31-82
 Plugging commenced 9-21-82
 Plugging completed 9-21-82

Reason for abandonment of well or producing formation
lack of oil
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
 Producing formation Arb Depth to top 3751 bottom 3753 T.D. 3753

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	152'	none
				5 1/2	3752	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. pumped 1 sx hulls down 5 1/2" & cemented with 70 sxs 50/50 Poz 6% gel 3% cc on bottom followed with 19 sxs gell & 80 sxs 50/50 Poz 6% gel 3% cc, squeezed at 1100#
cemented between 8 5/8" & 5 1/2" with 110 sxs 50/50 Poz 6% gel & 3% cc squeezed at 150# finished at 3:30 PM

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor none

STATE OF Kansas COUNTY OF Kansas, ss.
Stanley Freeman, (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stanley Freeman
 3120 Meadowlark, Gt Bend, Ks 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of Sept., 1982

Rita Baker
 Notary Public.

My Commission expires: 4-30-83



COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company TOMLINSON-KATHOL, INC.
Farm Lynd No. 6

32
SEC. 32 T. 9 R. 19W
Q 1/2 NE SW

Total Depth. 3753'
Comm. 7-17-61 Comp. 8-18-61
Shot or Treated.
Contractor. Tomlinson-Kathol, Inc.
Issued. 11-25-61

County Rocks KANSAS



CASING:
8 5/8" 152' cgm w/115 ex.
5 1/2" 3752'

Elevation. 2220' KB

Production. 46 BOPD

Figures Indicate Bottom of Formations.

clay - sand	60
clay - shale	130
shale	153
cement	163
shale	1636
Anhydrite	1670
shale	2747
lime - shale	3093
shale - lime	3198
lime - shale	3410
lime	3590
lime - shale	3620
lime	3623
shale - lime	3642
lime - chert	3698
cherty Conglomerate	3751
Arbuckle	3753 RTD
Total Depth	

TOPS:	
Topeka	3205
Heebner	3408
Toronto	3425
Lansing	3446
Conglomerate	3688
Arbuckle	3751

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1982

CONSERVATION DIVISION
Wichita, Kansas