

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rooks SEC. 32 TWP. 9 RGE. 19w E/W
Location as in quarters or footage from lines:
SW SE SW

Locate Well
correctly on above
Section Platt.

Lease Owner Kelso Casing Pulling
Lease Name Lynd #1 Well No. _____
Office Address Box 347, Chase, Ks. 67524
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 2/24/83
Plugging completed 3/2/83
Reason for abandonment of well or producing formation _____
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
Producing formation _____ Depth to top _____ bottom T.D. 3761'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	154'	none
				5 1/2"	3755'	1010'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with 5 sacks cement, sand to 3700' & 5 sacks cement.
Shot casing at 2000', 1736', 1400', & 1200', & 1000'. Pulled total of
24 joints. Plugged well with 4 hulls, 8 gel, 1 hull, 70 cement, 10 gel,
released plug & 70 cement. (50/50 pos. 6% gel)

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of MARCH, 1983

My Commission expires:



STATE CORPORATION COMMISSION
Irene Hoover Notary Public.
MAR 7 1983
3-7-83
CONSERVATION DIVISION
Wichita, Kansas

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- TOMLINSON-KATHOL, INC.
Farm- Lynd No. 1

SEC. 32 T. 9 R. 19W
SW SE SW

Total Depth. 3761'
Comm. 5-9-60 Comp. 5-23-60
Shot or Treated.
Contractor. Tomlinson-Kathol, Inc.
Issued. 9-24-60

County Rooks

KANSAS



Elevation. 2212' RB

Production. 42 BOPD

CASING:

8 5/8" @ 154' w/100 sks. cem.
5 1/2" @ 3755'

Figures Indicate Bottom of Formations.

sand-post rock	40
shale - sand	95
shale - clay	140
shale	175
chalky lime	270
shale	980
sand	1033
shale	1394
sand	1405
shale	1530
Anhydrite	1587
shale	2038
shale - lime	2180
lime & shale, sand	2325
shale - lime	2442
lime & shale	2805
shale & lime	2890
waxy shale	2980
shale	3141
shale - lime	3202
shale	3282
lime & sand lime, chert	3339
lime	3431
lime & chert	3463
lime	3727
shale & conglomerate	3752
shale & Arbuckle	3761 RTD
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1962

CONSERVATION DIVISION
Wichita, Kansas

<u>TOPS:</u>		SCOUT
		<u>TOPS:</u>
Topeka	3196	
Heebner	3403	3403
Toronto	3422	3423
Lansing	3441	3441
Base Kansas City	3646	3646
Conglomerate	3681	3681
Arbuckle	3754	3754