

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Continental Resources, Inc.  
Address: P.O. Box 1032, Enid, OK 73702  
Phone: 580+ 233-8955 Operator License #: 31914  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 7/26/06 (Date)  
by: Richard Lacy (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Chester Depth to Top: 6333 Bottom: 6352 T.D. 6600  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-175-20562-00-00  
Lease Name: Clark  
Well Number: 8-1  
Spot Location (QQQQ): \_\_\_\_\_ - SW - NE - NW  
660 Feet from  North /  South Section Line  
1980 Feet from  East /  West Section Line  
Sec. 8 Twp. 34 S. R. 34  East  West  
County: Seward  
Date Well Completed: 2/9/82  
Plugging Commenced: 7/28/06  
Plugging Completed: 8/2/06

ICCC  
Per GPS  
PKT  
4/14/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	1717	-----
				4 1/2"	6600	1810


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mix 200 lb hulls and 20 sx cement from 6333' to 6133'. Shot and pull to 1750', circulate hole w/mud. 50 sx cement from 1750' to 1600', 30 sx cement from 600' to 500', 10 sx from 40' to 0'. Capped 8 5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging Inc. License #: 31151  
Address: Rt #1, Box 49 BA, Tyrone, OK 73951-9731  
Name of Party Responsible for Plugging Fees: Continental Resources, Inc.  
State of Oklahoma County, Garfield, ss.

RECEIVED  
APR 02 2007  
KCC WICHITA

Zachary J. Harrel (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says that he has knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct. Amen. I do help me God.



(Signature) Zachary J. Harrel  
(Address) P.O. Box 1032, Enid, OK 73702

SUBSCRIBED and SWORN TO before me this 27 day of March, 20 07

Pamela R. Combest My Commission Expires: 3/8/2009 #01004021  
Notary Public

*[Handwritten initials]*