

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Continental Resources, Inc.
 Address: P.O. Box 1032, Enid, OK 73702
 Phone: 580+233-8955 Operator License #: 31914
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 8/3/06 (Date)
 by: Steve Pfeifer (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (if needed attach another sheet)
Chester Depth to Top: 6330 Bottom: 6340 T.D. 6450
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-175-20733-00-02
 Lease Name: Clark
 Well Number: 8-3
 Spot Location (QQQQ): - NW - NW
660 Feet from North / South Section Line
660 Feet from East / West Section Line
 Sec. 8 Twp. 34 S. R. 34 East West
 County: Seward
 Date Well Completed: 4/27/84
 Plugging Commenced: 8/4/06
 Plugging Completed: 8/7/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	1717	----
				4 1/2"	6450	2408


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 200 lb hulls and 20 sx cement 6330' to 6130'. Shot and pull 4 1/2" to 1750'. Circulate w/mud, 50 sx from 1750' to 1600', 30 sx from 600' to 500', 10 sx 40' to 0. Capped 8 5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging Inc. License #: 31151
 Address: Rt #1, Box 49 BA, Tyrone, OK 73951-9731
 Name of Party Responsible for Plugging Fees: Continental Resources, Inc.
 State of Oklahoma County, Garfield, ss.

RECEIVED
APR 02 2007
KCC WICHITA

Zachary J. Harrel (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, say that I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Zachary J. Harrel
 (Address) P.O. Box 1032, Enid, OK 73702

SUBSCRIBED and SWORN TO before me this 27 day of March, 20 07
Pamela R. Combest My Commission Expires: 3/8/2009 #01004021
 Notary Public

PK