

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Pintail Petroleum, Ltd.
Address: 225 N Market, #300, Wichita, KS 67202
Phone: (316) 263-2243 Operator License #: 5086
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Doug Louis (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15 - 077-21420 -00-00
Lease Name: Wilson Trust
Well Number: 2
Spot Location (QQQQ): SW - SW - NW -
2970 Feet from North / South Section Line
4950 Feet from East / West Section Line
Sec. 16 Twp. 33 S. R. 6 East West
County: Harper
Date Well Completed: 12-8-2001
Plugging Commenced: 3-9-2007
Plugging Completed: 3-13-2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	252	
				4 1/2	4499	3420

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Sand was at 4370', bailed 4 sacks cement with bailer, pulled slips, had 32" stretch, ripped casing at 3630', worked pipe, ripped casing at 3420', came free, pulled up to 1200', pumped 35 sacks, pulled up to 700', pumped 35 sacks, pulled up to 300', circulated with 110 sacks, pulled rest of casing, tore down floor and rig.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67526

RECEIVED
MAR 30 2007

Name of Party Responsible for Plugging Fees: Pintail Petroleum, Ltd.
State of Kansas County, Sedgwick, ss.

KCC WICHITA

Walter Innes Phillips (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Walter Innes Phillips
(Address) 225 N. Market #300 Wichita KS 67202

SUBSCRIBED and SWORN TO before me this 22nd day of March, 2007
[Signature] My Commission Expires: 12/11/2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT