

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION  
Address: 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206  
Phone: (316) 682-1537 Operator License #: 5030  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 11/1/06 (Date)  
by: Barry Metz (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
LKC Depth to Top: 3538 Bottom: 3616 T.D. 3733  
Arb Depth to Top: 3706 Bottom: 3733 T.D. 3733  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-163-00729-00-00  
Lease Name: Trico LKC Arbuckle Unit  
Well Number: #302  
Spot Location (QQQQ): \_\_\_\_\_ - NW - NW - SE  
2310' Feet from  North /  South Section Line  
2310' Feet from  East /  West Section Line  
Sec. 33 Twp. 10 S. R. 20  East  West  
County: Rooks  
Date Well Completed: 11/54  
Plugging Commenced: 2/23/07  
Plugging Completed: 2/23/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	180	
				5-1/2	3707	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged and abandoned. Perforated at 850', 1600', 2150'. Ran tubing to 3710'. Spotted 60 sx 60/40 poz w/8% gel w/450# hulls. Pulled tubing to 2790' and pumped 100 sx cement w/200# hulls. Pulled tubing to 1250' and pumped 160 sx cement w/150 # hulls and circulated to surface. TOH w/tubing. Connected to 5 1/2" and 8 5/8" annulus and pumped 20 sx cement. SI - 400#.

Topped off casing w/20 sx cement. 360 sx total. Approved by KCC.

Name of Plugging Contractor: Smoky Hills Well Service License #: 32452  
Allied Cementing Co., Inc.  
Address: P.O. Box 31, Russell, KS 67665-0031


Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County, Sedgwick, ss.


Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_  
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 15th day of March  
Michelle Henning My Commission Expires: \_\_\_\_\_  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



KCC PR 3/27/07  
Per CP 2/3


Per

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 MAR 19 2007  
 CONSERVATION DIVISION  
 WICHITA, KS

TRANS ERA #2 VEACH 33-10-20W  
 NW NW SE  
 Contr. TRANS ERA ROOKS County  
 2131 RB Comm. Comp. 12-17-54 IP 203 BOPD  
 PERM PMPG

Tops	Depth	Datum
HIEEB	3368	-1237
KC	3405	-1274
GONG	3653	-1522
ARB	3706	-1575
TD	3709	-1578

Casing  
 8" 180  
 5" 3706  
 DST 3484-93/1 HR, 30' MDY SW  
 BHP 550#  
 DST 3707-09/1 HR, 1800' FREE  
 OIL, BHP 995#  
 CO 3709: ACID 500: 5 1/2 BOPH  
 NAT'L: SWB 20 BOPH, NO WTR  
 ALLPHIN POOL DD 3720 70



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

# ALLIED CEMENTING CO., INC.

33023

483-9169

P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>2-23-07</u>	SEC. <u>33</u>	TWP. <u>10S</u>	RANGE <u>20W</u>	CALLED OUT	ON LOCATION <u>9:30am</u>	JOB START <u>10:00am</u>	JOB FINISH <u>12:30</u>
LEASE <u>Truck</u>	WELL # <u>302</u>	LOCATION <u>El-S-N - Co. line 1/2 N E 5 into</u>		COUNTY <u>Roys</u>	STATE <u>KS</u>		

OLD OR NEW (Circle one)

CONTRACTOR Smoky Hill

TYPE OF JOB Old Hole Plug

HOLE SIZE \_\_\_\_\_ T.D. 3733'

CASING SIZE 5/2 DEPTH \_\_\_\_\_

TUBING SIZE 3/2 DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

**EQUIPMENT**

PUMP TRUCK CEMENTER Craig

# 409 HELPER Adrian

BULK TRUCK

# 362 DRIVER Steve

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**

1st Plug 3710 - 60% 450# HULLS

2nd 2790 100% 200 HULLS

3rd 1250 160% 150 HULLS - Circulate Cement!

Min 20% down Backside Shut in 400PSI

Max 20% down 5/2 & fill up.

*Thanks!*

CHARGE TO: Vessel

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 19 2007

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE

*James Hacht*

OWNER \_\_\_\_\_

CEMENT AMOUNT ORDERED Used 360% 450 #/100 100% Gel 800# HULLS

COMMON	<u>216</u>	@	<u>10.65</u>	<u>2300.40</u>
POZMIX	<u>144</u>	@	<u>5.80</u>	<u>835.20</u>
GEL	<u>31</u>	@	<u>16.65</u>	<u>516.15</u>
CHLORIDE		@		
ASC		@		
<u>Hulls</u>	<u>8</u>	@	<u>25.50</u>	<u>204.00</u>
HANDLING	<u>505</u>	@	<u>1.90</u>	<u>959.50</u>
MILEAGE	<u>.07 / sk / mile</u>			<u>2863.35</u>
TOTAL				<u>7678.60</u>

**SERVICE**

DEPTH OF JOB				
PUMP TRUCK CHARGE				<u>720.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>63</u>	@	<u>6.00</u>	<u>378.00</u>
MANIFOLD		@		
TOTAL				<u>1098.00</u>

**PLUG & FLOAT EQUIPMENT**

	@		
	@		
	@		
	@		
	@		

TOTAL 4836.00

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME