

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: White Pine Petroleum Corp.

Address: 110 S Main, Suite 500, Wichita, KS 67202-3745

Phone: (316) 262-5429 Operator License #: 5044

Type of Well: Oil, Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3-7-07 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Douglas lime Depth to Top: 3618 Bottom: 3623 T.D. \_\_\_\_\_  
Douglas sand Depth to Top: 3668 Bottom: 3672 T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-007-21201-00-01

Lease Name: Lukens

Well Number: 2

Spot Location (QQQQ): \_\_\_\_\_ - SW - SE - NE  
2970 Feet from  North /  South Section Line

990 Feet from  East /  West Section Line

Sec. 28 Twp. 32 S. R. 11  East  West

County: Barber

Date Well Completed: 11-8-89

Plugging Commenced: 3-5-07

Plugging Completed: 3-7-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	263	
				5 1/2	3803	2870

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3570', bailed 5 sacks cement with bailer, pulled slips, had 17" stretch, cut surface off 4' below ground, ripped casing at 2870', worked pipe free, pulled casing up to 600', pumped 15 gel, 50 sacks, pulled to 270', pumped 50 sacks, pulled to 40', circulated with 15 sacks.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 401 W. Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: White Pine Petroleum Corp.

State of KANSAS County, SEDGWICK, ss.

Wilbur C. Bradley (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Wilbur C Bradley

(Address) 110 S. MAIN, SUITE 500, WICHITA, KS 67202



SUBSCRIBED and SWORN TO before me this 19th day of March, 2007

Richard A. Pape, Jr. My Commission Expires: 8/14/2008  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

MAR 20 2007

KCC WICHITA

PKT