

7-5

15-163-01646-00-00

4-041692

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1-1951

NE NW SW/4 SEC. 14, 09 S, 19 W
2310 feet from S section line
4290 feet from E section line

Operator license# 5635

Lease: Kaba Well # 3

Operator: The Gene Brown Company

County: Rooks

Address: P.O. Drawer #220
Plainville, Kansas 67663

Well total depth 3499 feet
Conductor Pipe: 0 inch @ 0 ft
Surface pipe 8⁵/₈ Inch @ 1498 ft
w/850 sxs.

113.72

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# _____

Address: Russell, Kan 67665

Company to plug at: Hour: 8:00 A.M. Day: 5 Month: July Year: 1995

Plugging proposal received from: Tom Brown

Company: The Gene Brown Company Phone: _____

Were: 5 1/2" casing set at 3495' w/200 sxs. cement. W.L.M. 3498'. T.O.F. at 1600'.
Ordered 350 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[] , Part[X] , None[]

Completed: Hour: 12:00 P.M. , Day: 5 , Month: July , Year: 1995

Actual plugging report: Rig up cementers to 8 5/8" casing. Squeezed with 100 sxs. cement.
Max. P.S.I. 500#. Rig up cementers to pump down casing with 225 sxs. 60/40 pozmix - 10% gel
with 300# hulls. Max. P.S.I. 1000#. S.I.P. 700#.

Remarks: _____

Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____

Bottom plug(in place): YES X , CALC _____ , NO _____ Dakota plug: YES X , NO _____

Plugged through TUBING _____ , CASING X . Elevation: _____ GL

I did[X] / did not[] observe the plugging.

Dennis J. Hamel
(agent)

RECEIVED
STATE CORPORATION COMMISSION
7-21-95
JUL 21 1995
Form CP-2/3 1995

INVOICED
DATE 7-25-95
INV. NO. 43159
7-5

100