

6 031399

359 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-01642-00-00

NW SW SE, SEC. 14, T 9 S, R 19 W
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Boisvert Well # 6

Operator: Phillips Pet. Co.
Name & Address Box 20 A Route #3
Great Bend, Ks. 67530

County Rooks 114.43
Well Total Depth 3521 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1495

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 25 Month: July Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone) _____

were: 8 5/8 set at 1495 w/875 sks. 5 1/2 set at 3492 w/200 sks.

4 1/2 liner set at 3521 w/40 sks. Perfs 3296 - 3507. OH. 3492 - 3512. Order sand and com
mon cement. Pull pipe. Order 225 sks 65/35 poz 8% gel. 500 # hulls.

Allied Cement Co. ows Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15Pm Day: 25 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3240 w/5sks common cement on sand w/bailer.

Recovered 2300' of 5 1/2 casing. Sq 8 5/8 w/225 sks cement blend with 500 lbs.
hulls mixed in to max psi 700 lbs. Close in psi 300 lbs.

Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
8-7-90
AUG - 7 1990

Remarks: _____
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
(did not observe this plugging.)
AUG 15 1990

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

DATE: _____
INV. NO. 28932
7-25

SEP 14 1990
gls.