

7-5

15-163-03000-00-00

4-041693

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 12-6-1951

NE SW SW/4 SEC. 14, 09 S, 19 W
990 feet from S section line
4290 feet from E section line

Operator license# 5635

Lease: Kaba Well # 7

Operator: The Gene Brown Company

County: Rooks

113.95

Address: P.O. Drawer #220
Plainville, Kansas 67663

Well total depth 3506 feet
Conductor Pipe: 0 inch @ 0 ft
Surface pipe 8% Inch @ 1898 ft
w/180 sxs.

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# _____

Address: Russell, Kan 67665

Company to plug at: Hour: 10:00A.M. Day: 5 Month: July Year: 1995

Plugging proposal received from: Tom Brown

Company: The Gene Brown Company Phone: _____

Were: 5 1/2" casing set at 3499' w/150 sxs. cement. Anhy. at 1464' with 550 sxs. W.L.M. at 3505'. T.O.F. at 1700'. Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 9:30 A.M., Day: 5, Month: July, Year: 1995

Actual plugging report: Hooked-up to 8 5/8" S.P and annulus. Pressured-up to 500#. Hooked-up to 5 1/2" casing and squeezed down with 250 sxs. cement with 300# hulls in cement. Max. P.S.I. 700#. S.I.P. 300#.

Remarks: _____

Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING X. Elevation: _____ GL _____

I did[X] / did not[] observe the plugging.

Dennis J. Hamel
(agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1995
7-21-95

WICHITA
Form CP-2/3

INVOICED

DATE 7-25-95

INV. NO. 43160

7-5

1000